

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-21360-00-00  
Spot: NWNW Sec/Twnshp/Rge: 3-29S-12W  
660 feet from N Section Line, 660 feet from W Section Line  
Lease Name: BERGNER Well #: 1  
County: PRATT Total Vertical Depth: 4660 feet

Operator License No.: 30705  
Op Name: YOUNGER ENERGY COMPANY  
Address: 453 S. WEBB RD., STE 100  
WICHITA, KS 67207

PROD Size: 5.5 feet: 4381 WITH 75 SX CMT  
SURF Size: 8.625 feet: 433 WITH 300 SX CMT

#151 45

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/08/2005 1:30 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND BOTTOM TO 4170' & 4 SX CMT. PLUG AT 760' WITH 10 SX GEL & 50 SX CMT. PLUG AT 460' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/08/2005 2:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 4170' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 760' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 460' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4261	4270		
4222	4226		

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUL 15 2005  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2860' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

*Stephen J. Pfeifer*  
(TECHNICIAN)

INVOICED

DATE 7-18-05

INV. NO. 2006060059

Form CP-2/3