

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-21660-00-00  
Spot: SWSE Sec/Twnshp/Rge: 36-29S-7W  
660 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: COYKENDALL Well #: 9  
County: KINGMAN Total Vertical Depth: 4220 feet

Operator License No.: 5123  
Op Name: PICKRELL DRILLING COMPANY, INC.  
Address: 100 SOUTH MAIN - SUITE 505  
WICHITA, KS 67202

PROD Size: 4.5 feet: 4217 125 SX CMT  
SURF Size: 8.625 feet: 233 145 SX CMT

#139<sup>15</sup>

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/27/2005 10:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PBTD 4185'; 4136 - 4141 squeezed; cmt retainer 4126, 4090 - 4098; sand to 4040'; 35 sxs @ 1100'; 35 sxs @ 700'; and circ 285'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 06/27/2005 12:45 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perforations covered with sand to 4040' and 4 sacks of cement. Recovered 3230' of 4-1/2" casing. Pulled to 1100' and spotted 35 sacks of cement. Pulled to 700' and spotted 35 sacks of cement. Pulled to 285' and circulated cement to surface.

Allied #16349

60/40 posmix with 4% gel

Perfs:

Top	Bot	Thru	Comments
4136	4141		
4090	4098		


**RECEIVED  
KCC DISTRICT #2  
JUL 13 2005  
WICHITA, KS**

Remarks:

Plugged through: CSG

District: 02

Signed \_\_\_\_\_



(TECHNICIAN)

RECEIVED  
JUL 18 2005  
KCC WICHITA

INVOICED  
DATE 7-18-05  
INV. NO. 206060053