

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-21,491-00-00

LEASE NAME Worcester

WELL NUMBER F-16-1

 Ft. from S Section Lin

 Ft. from E Section Lin

SEC. 16 TWP. 7 RGE. 22 (E) or (W)

COUNTY Graham

Date Well Completed 10-25-81

Plugging Commenced 1-21-92

Plugging Completed 6:00PM

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Central energy Corp.

ADDRESS Box 47590, Wichita, Ks 67202

PHONE# (316) 267-0707 OPERATORS LICENSE NO. 9354

Character of Well Oil

(Oil), Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-21-92 (date)

by Carl Goodrow (KCC District Agent's Name)

Is ACO-1 filed? NA If not, Is well log attached? NA

Producing Formation Lansing Depth to Top 3600 Bottom 3608 T.D. 3895

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	275	0
				5 1/2	3880	828

JAN 28 1992
JAN 28 1992
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plug was used, state the character of same and depth placed, from feet to feet each s
Bottom plug: Sanded to 3550 & bailed 5 sx cement.

Top plug: Perforated at 1927 ft, ran tubing & spotted 40 sx 65/35 w 10% gel & 100 lbs Hulls Perforated at 1201 ft & spotted 20 sx c. Pulled tubing & shot 5 1/2 at 828 ft, spotted 50 sx c, pulled up to 300 ft & circulated to surface -
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. 4635 CP

Address Box 251, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Central Energy Corp.

STATE OF Kansas COUNTY OF Barton, ss.


Anna K. Burke

(Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein, and matters herein contained and the log of the above-described well as filed with the same are true and correct, so help me God.

(Signature) Anna K. Burke

(Address) Box 251, Great Bend, Kansas 67530

SUBSCRIBED AND SWORN TO before me this 27 day of January, 19 92



My Commission Expires: 4-30-93

Gary G. Burke
Notary Public

with 125 sx cement. Pulled casing & topped off w/15 sx cement.