

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: V.J.I. Natural Resources Inc.
Address: 30-38 48th St. Astoria, New York 11103
Phone: (785) 625 8360 Operator License #: 30420
Type of Well: Dry D&A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 1-31-05 (Date)
by: Mr. Lacy (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-145-21509-00-00
Lease Name: Josefiak
Well Number: 1-A
Spot Location (QQQQ): _____ - SW - SW - SW
450 Feet from North / South Section Line
450 Feet from East / West Section Line
Sec. 35 Twp. 22 S. R. 17 East West
County: Pawnee
Date Well Completed: 1-31-05
Plugging Commenced: 1-31-05
Plugging Completed: 1-31-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Surface		0	820	8 5/8"	820	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1st Plug at 1100' w/80sks 60/40 poz 6% Gel
2nd Plug at 400' w/50sks 60/40 poz 6% Gel
3rd Plug at 40' w/10sks 60/40 poz 6% Gel
Plug Rat Hole w/15sks 60/40 poz 6% Gel

RECEIVED
JUL 12 2005
KCC WICHITA
RECEIVED
JUL 12 2005
KCC WICHITA

Name of Plugging Contractor: Acid Services, LLC License #: 32453
Address: 10244 NE Highway 61, P.O. Box 8613, Pratt, Kansas 67124
Name of Party Responsible for Plugging Fees: V.J.I. Natural Resources Inc.
State of New York County, _____, ss.

Jason Dinges (agent) (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Jason Dinges
(Address) 1584 Smokey Hill River Rd., Hays, Ks. 67601

SUBSCRIBED and SWORN TO before me this 30 day of June, 2005
Christine Schlyer My Commission Expires: 10-12-06
Notary Public



SALES OFFICE:
 100 S. Main
 Suite #607
 Wichita KS 67202
 (316) 262-3699
 (316) 262-5799 FAX

COPY

SALES & SERVICE OFFICE:
 10244 NE Hiway 61
 P.O. Box 8613
 Pratt, KS 67124-8613
 (620) 672-1201
 (620) 672-5383 FAX

SALES & SERVICE OFFICE:
 1700 S. Country Estates Rd.
 P.O. Box 129
 Liberal, KS 67905-0129
 (620) 624-2277
 (620) 624-2280 FAX

Invoice

Bill to: VJI Natural Resources c/o Jason Dinges 1584 Smokey Hill River Rd. Hays, KS 67601	9055000	Invoice	Invoice Date	Order	Order Date
		501150	1/31/05	9198	1/31/05
Service Description					
Cement					
Lease				Well	
Josefiak				A-1	
AFE	CustomerRep	Treater	Well Type	Purchase Order	Terms
	K. Roach	T. Seba	New Well		Net 30

<u>ID.</u>	<u>Description</u>	<u>UOM</u>	<u>Quantity</u>	<u>Unit Price</u>	<u>Price</u>
D203	60/40 POZ (COMMON)	SK	155	\$9.09	\$1,408.95 (T)
C320	CEMENT GELL	LB	536	\$0.25	\$134.00 (T)
E100	HEAVY VEHICLE MILEAGE - 1 WAY	MI	50	\$3.65	\$182.50 (T)
E101	CAR, PICKUP OR VAN MILEAGE - 1 WAY	MI	50	\$2.15	\$107.50 (T)
E104	PROPPANT / BULK DELIV SERVICES/TON MILE, \$200 MIN	TM	335	\$1.60	\$536.00 (T)
E107	CEMENT SERVICE CHARGE	SK	155	\$1.50	\$232.50 (T)
R400	CEMENT PUMPER, PLUG & ABANDON (Workover Unit) 2 HR	EA	1	\$700.00	\$700.00 (T)

Sub Total:	\$3,301.45
Discount:	\$825.36
Discount Sub Total:	\$2,476.09
Pawnee County & State Tax Rate: 6.30%	Taxes: \$155.99
<i>(T) Taxable Item</i>	Total: \$2,632.08

RECEIVED
 JUL 12 2005
 KCC WICHITA

PLEASE REMIT TO Acid Services, LLC, Dept No 1131 , Tulsa, OK 74182

Accounts become past due the last day of the month following billing. Interest rate 1.5% per month (18% per year) on past due accounts.



TREATMENT REPORT

Customer ID		Date	
Customer V.J.I. NAT. RES		1-31-05	
Lease JOSEPIAK		Lease No.	Well # A-1
Field Order # 9198	Station PRATT	Casing 4 1/2	Depth 1100'
Type Job P.T.A. NEW WELL		Formation ID= 4190'	Legal Description 35-22S-17W
		County PAWNEE	State Ks

PIPE DATA		PERFORATING DATA		FLUID USED		TREATMENT RESUME		
Casing Size	Tubing Size	Shots/Ft		Acid- 155 SK 60/40 P02	RATE	PRESS	ISIP	
Depth	Depth	From	To	Pre Pad 6% GEL	Max		5 Min.	
Volume	Volume	From	To	Pad 13.3' / GAL 1.59 ft³	Min		10 Min.	
Max Press	Max Press	From	To	Frac	Avg		15 Min.	
Well Connection	Annulus Vol.	From	To	Flush	HHP Used		Annulus Pressure	
Plug Depth	Packer Depth	From	To		Gas Volume		Total Load	

Customer Representative	Station Manager D. AUSTIN	Treater J. SEBA
-------------------------	----------------------------------	------------------------

Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log
14:00		RECEIVED			
16:30		JUL 12 2005			CALLER CAL
		KCC WICHITA			ON LOC WITH K's: SAFETY MTG
19:55	150		15	4 1/2	1ST Plug 1100' 80 SK 60/40 P02 6% GEL
20:05	0		22.6		Pump H2O
			9.7		MIX: Pump 80 SK d 13.3' / GAL
					Ball DISP
20:44	100		5	3	2ND Plug 400' 50 SK 60/40 P02 6% GEL
			14.1		Pump H2O
20:50	0		2		MIX: Pump 50 SK d 13.3' / GAL
					Ball DISP
21:15			2.83	2	3RD Plug 40' 10 SK 60/40 P02 6% GEL
					MIX: Pump 10 SK d 13.3' / GAL
					CTRL CONT TO SURFACE
			4.24	1	Plug & Hole 15 SK 60/40 P02 6% GEL
21:30					JOB COMPLETE

THANKS TOO