

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: A G V Corp.
Address: 123 N Main Attica, ks 67009
Phone: (620) 254-7222 Operator License #: 5039
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 10-18-2001 (Date)
by: _____ (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Douglas Depth to Top: 3416 Bottom: 3450 T.D. 3509

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-077-20911-00-00
Lease Name: Ferrell
Well Number: 5
Spot Location (QQQQ): SW-NE
1980 Feet from North / South Section Line
1510 Feet from East / West Section Line
Sec. 24 Twp. 32 S. R. 9 East West
County: Harper
Date Well Completed: 08-05-1983
Plugging Commenced: 10-23-2001
Plugging Completed: 10-24-2001

KCC
BEM
7-14-05
RBMS

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Douglas	Gas/Water	3416	3450	4 1/2	3509	2515'
Surface				8 5/8	259	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set Bridge Plug 3390, Shot casing off at 2515, pump 35 sx at 1306'
Pumped 35 sx at 825', Cement to surface from 350' with 120 sx
Cement surface with 10 sx

Name of Plugging Contractor: Shawnee Well Service Inc License #: 30346
Address: P. O. Box 781624 Wichita, Ks 67278

Name of Party Responsible for Plugging Fees: A G V Corp.
State of Kansas County, Harper, ss.

Larry G Mans (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Larry G Mans

(Address) 123 N Main Attica Ks 67009

SUBSCRIBED and SWORN TO before me this 12th day of July, 2005

Agnes Eck My Commission Expires: Oct 7, 2007
Notary Public

RECEIVED

JUL 13 2005

KCC WICHITA

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

AGNES ECK
Notary Public - State of Kansas
My Appt. Expires 10-7-2007

BW

116 1/2" CI CHECK
 2" LINE PIPE
 2000 90DEG
 WANK OIL F
 1 1/2% PER
 NET 30

INVOICE

LOG-TECH, INC.
 1011 240th Ave.
HAYS, KANSAS 67601
 (785) 625-3858

8446

Date 10-24-01

CHARGE TO: AGV

ADDRESS _____

R/A SOURCE NO. _____ CUSTOMER ORDER NO. OW

LEASE AND WELL NO. Ferrill FIELD _____

NEAREST TOWN _____ COUNTY Harper STATE Ks.

SPOT LOCATION _____ SEC. 24 TWP. 32s RANGE 9w

ZERO 5' AGL CASING SIZE 4 1/2" WEIGHT _____

CUSTOMER'S T.D. _____ LOG TECH _____ FLUID LEVEL _____

ENGINEER R. Schneider OPERATOR Ernst

PERFORATING				
Description	No. Shots	From	Depth To	Amount
<u>C-10 csg shot @ 252</u>				<u>80000</u>
<u>- 6</u>				
<u>2515</u>				

DEPTH AND OPERATIONS CHARGES				
Description	From	Depth To	Total No. Ft.	Price Per Ft. Amount
<u>4 1/2" Bridge Plug</u>				<u>550 00</u>
<u>setting charge @ 3390'</u>				<u>- 7</u>
				<u>3383 00</u>
<u>T.J. 8:00 Dumphaibe (2 sks)</u>				<u>.16 542 40</u>
<u>A.O.L. 7:50</u>				
<u>S.J. 8:20</u>				
<u>F.J. 10:30</u>				
<u>T.W.L. - 0'</u>				

MISCELLANEOUS		
Description	Quantity	Amount
Service Charge	RECEIVED	<u>450 00</u>
	JUL 13 2005	
	KCC WICHITA	

PRICES SUBJECT TO CORRECTION BY BILLING DEPARTMENT

RECEIVED THE ABOVE SERVICES ACCORDING TO THE TERMS AND CONDITIONS SPECIFIED ON THE REVERSE SIDE TO WHICH WE HEREBY AGREE.

Customer Signature Martin Coppe Date _____

Sub Total 2884 80

Code Ref. _____ IF PAID WITHIN 10 DAYS
 PAY DISCOUNT AMOUNT 1875 00

Tax _____

pd 11/24/01

ck # 3762



P.O. BOX 333 ATTICA, KANSAS 67009
316-254-7893

FIELD REPORT

Date 10-24-01

Company Attica Gas Venture
Lease Ferrell Well No. #5
Job Type Casing Job County Harper
Unit No. 4 Foreman Terry Klick
NWC _____ SWD _____ Working TD _____

	FOREMAN/UNIT	FLOOR HANDS	EXTRA MEN	OVERNITE CHARGE
No.	1	2	1	
Hours	12	12	12	

EQUIPMENT & SERVICES

TUBING TONG, ONE WAY TRIP(S) 1 (EXPLANATION) pulled casing, layed down
 PIPE DOPE: 1 BUCKETS TYPE: _____ ALUMINUM PAINT _____ QTS.
 DIESEL _____ GALS. SOLVENT: 5 GALS. OIL SAVER RUBBERS _____ STRIPPING RUBBERS _____
 SWAB CUPS: No. _____ TYPE: _____
 No. _____ TYPE: _____
 CASING TONG, ONE WAY TRIP(S) _____ (EXPLANATION) _____
 CASING TOOLS _____

SPECIAL TOOLS / SERVICES

SAND PUMP _____ BAILER _____ ROD FISHING TOOLS _____
 CHANGE OVER SUB _____ BIT: _____ MASTER GATE VALVE _____
 STANDING VALVE _____ SLIPS & ELEVATORS 4 1/2" casing
 SWAB TANK _____ POWER REVERSE UNIT _____ OTHER _____

JOB DESCRIPTION Drove to location, started rig. Worked casing for stretch. Rig up logging truck. Set plug, and spotted cement. Shot casing off at 2515'. Pulled 28 joints to 1st plug back at 1306'. Waited on cementers, pumped 1st plug. Pulled 11 joints to 2nd plug back at 841.85. Pulled 12 joints to 3rd plug back at 335.52. Pulled remaining 8 joints total of 60 joints. Cemented surface pipe. Changed back over to pullrods. Cleaned up tools. Rig down, Drove to shop.

WELL RECORD

EQUIPMENT	FEET OR JOINTS	PULLED FROM WELL		EQUIPMENT	FEET OR JOINTS	RERAN IN WELL	
		Description				Description	
POLISHED ROD	<u>4 1/2 plug</u>	<u>3390</u>		MUD ANCHOR			
ROD SUBS				SEATING NIPPLE			
RODS	<u>1st plug</u>	<u>1306.48</u>		TUBING			
RODS				TUBING SUBS			
PUMP	<u>2nd plug</u>	<u>841.85</u>		GAS ANCHOR			
GAS ANCHOR				PUMP			
TUBING SUBS	<u>3rd plug</u>	<u>335.52</u>		RODS			
TUBING				RODS			
SEATING NIPPLE				ROD SUBS			
MUD ANCHOR				POLISHED ROD			
<u>Casing</u>	<u>60</u>	<u>4 1/2"</u>					
PROD. PACKER				PROD. PACKER			
TUBING ANCHOR				TUBING ANCHOR			

RECEIVED
JUL 13 2005
KCC WICHITA

ALLIED CEMENTING CO., INC.

08592

Federal Tax I.D.# ~~XXXXXXXXXX~~

P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Med hodge

DATE <u>10.24.01</u>	SEC. <u>24</u>	TWP. <u>32N</u>	RANGE <u>9W</u>	CALLED OUT <u>10:00 A.M</u>	ON LOCATION <u>1:45 pm</u>	JOB START <u>2:30</u>	JOB FINISH <u>4:15</u>
LEASE <u>Ferrell</u>	WELL # <u>5</u>	LOCATION <u>Attica 1 1/4 W on 160 E into</u>		COUNTY <u>Harper</u>	STATE <u>KS</u>		
<input checked="" type="radio"/> OLD OR <input type="radio"/> NEW (Circle one)							

CONTRACTOR Shawnee Well Svc

TYPE OF JOB OHP

HOLE SIZE 7 7/8 T.D. _____

CASING SIZE 8 5/8 DEPTH 300'

TUBING SIZE _____ DEPTH _____

~~DRILL PIPE~~ CSG. 4 1/2 DEPTH 1300'

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT Fresh H2O

EQUIPMENT _____

PUMP TRUCK CEMENTER Shane Winsor

352 HELPER David Felio

BULK TRUCK _____

353- DRIVER Chris Lunsford

BULK TRUCK _____

_____ DRIVER _____

OWNER Attica Gas Ventures

CEMENT

AMOUNT ORDERED 200 sx 60:40:4

COMMON	<u>126</u>	@	<u>6.65</u>	<u>837.90</u>
POZMIX	<u>34</u>	@	<u>3.55</u>	<u>298.20</u>
GEL	<u>7</u>	@	<u>10.00</u>	<u>70.00</u>
CHLORIDE		@		
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>217</u>	@	<u>1.10</u>	<u>238.70</u>
MILEAGE	<u>217 x 19</u>		<u>-04</u>	<u>164.92</u>
				TOTAL <u>1609.72</u>

REMARKS:

On location Rig up - 2:30 pm load hole w/
15 bbl Fresh H2O pump 35sx plug at
1300' - 3:05 load hole w/ Fresh H2O
8 bbl. Pump 35sx Plug at 825' - 3:45
load Hole w/ 6 bbl Fresh H2O circ. cement
to surface from 350' w/ 130sx cement
top out w 10sx 4:15

SERVICE

DEPTH OF JOB	<u>1300'</u>		
PUMP TRUCK CHARGE			<u>475.00</u>
EXTRA FOOTAGE		@	
MILEAGE	<u>19</u>	@	<u>3.00</u>
PLUG		@	
		@	
		@	

CHARGE TO: Attica Gas Venture

STREET _____

CITY _____ STATE _____ ZIP _____

RECEIVED

JUL 13 2005

FLOAT EQUIPMENT

KCC WICHITA

TOTAL 532.00

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE Jerry Klick

TAX 137.07

TOTAL CHARGE 2278.79

DISCOUNT 214.17 IF PAID IN 30 DAYS

2064.62

TERRY KLICK

PRINTED NAME