


15-065-00464-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Graham County, Sec. 28 Twp. 7 Rge. 21 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines NE NE NE  
Lease Owner Trans Era Petroleum, Inc.  
Lease Name Sayer "B" Well No. 1  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 5/31/54 19  
Application for plugging filed 5/30/54 19  
Application for plugging approved 5/30/54 19  
Plugging commenced 5/31/54 19  
Plugging completed 5/31/54 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3699 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	207	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

PLUGGING RECORD

Lay down drill pipe, filled hole with heavy mud to 200', set bottom plug at 200' with one-half sack of hulls and 15 sacks of cement used. Filled hole with heavy mud to 40' set top plug at 40' with one-half sack of hulls and 10 sacks of cement used.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 12, 1954  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Trans Era Petroleum, Inc.  
Address Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
H. R. Michaelis (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *H. R. Michaelis*  
Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 4th day of June, 19 54

*Margie Cooper*  
Notary Public.

My commission expires 1-30-57

PLUGGING  
FILE SEC 28 T 7 R 21W  
BOOK PAGE 38 LINE 20

Trans Era Petroleum, Inc.  
Sayer "B" #1

NE NE NE 28-7-21  
Graham County, Kansas

Total Depth 3699'  
Comm. 5/21/54  
Comp. 5/31/54

Casing

8 5/8" Set @ 207'

Cement

135 sacks Lone Star

Formation	Depth
Clay-sand-shale	206
Shale-sand	1455
Shale-red bed	1710
Anhydrite	1740
Shale-shells	2145
Shale-lime	3290
Lime	3552
Lime-shale	3600
Shale	3608
Chert-shale	3645
Conglomerate	3649
Arbuckle	3699'

STATE OF KANSAS }  
                          } ss  
RUSSELL COUNTY }

I hereby certify that the above information is true and correct to the best of my knowledge.

*Cass Burt*  
-----

Subscribed and sworn to before me this 4th day of June, 1954.

*Margie Cooper*  
-----  
Notary Public

My commission expires: 1-30-57.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 12 1954  
JUN 12 1954

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE NO. 2817 HW  
BOOK PAGE 38 LINE 20