

15-065-01032-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Graham County. Sec. 31 Twp. 7S Rge. 21W (E) (W)

Location as "NE/CNW/SW" or footage from lines NW NE SE

Lease Owner Wilson Exploration Company

Lease Name SAYER Well No. 1-A

Office Address Sinclair Building, Fort Worth, Texas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 22, 1962

Application for plugging filed June 22, 1962

Application for plugging approved June 22, 1962


Plugging commenced June 22, 1962

Plugging completed June 22, 1962

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty, Box 326, Hays, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3713 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	234'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set bridge @540' w/1/2 Sx. hulls on top and 20 Sx. cement. Fill hole with mud to 230'.
Set bridge w/ 1/2 Sx. hulls on top and 20 Sx. cement. Fill hole w/mud to 40'.
Bridge and 10 Sx. cement.
2 Sx. cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
JUL 21 1962
JUL 2 1962
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Raymond Oil Company, Inc.

Address 410 Fourth National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF Sedgwick, ss.
Patrick R. Raymond (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Patrick R. Raymond

410 Fourth National Bank Building, Wichita, Ks

(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of June, 19 62

Bernice Boldt

Notary Public.

My commission expires December 10, 1962



Wilson Exploration Company
 No. 1-A SAYER
 NW NE SE 31-7S-21W
 Graham County, Kansas

ELEVATION: 2123 KB

Casing Record:
 8-5/8" w/200 Sx.

Contractor: Raymond Oil Company, Inc. - Rig #1
 Commenced: May 15, 1962
 Completed: May 22, 1962

Figures Indicate Bottom of Formation

<u>Formation</u>	<u>Depth</u>
Shale	190
Shale and Shells	1230
Sand	1445
Red Rock	1723
Anhydrite	1755
Shale and Shells	1995
Shale with Lime	2075
Shale and Lime	3335
Lime	3390
Lime and Shale	3455
Lime	3530
Lime with Shale	3580
Lime and Shale	3713 TD

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 2, 1962
 JUL 2, 1962
 CONSERVATION DIVISION
 Wichita, Kansas

TOPS

Anhydrite	1723
Heebner	3307
Lansing	3346
Conglomerate (Chert)	3642
Arbuckle	3665
Rotary Total Depth	3713

STATE OF KANSAS)
)SS.
 COUNTY OF SEDGWICK)

I hereby certify that the above is true and correct to the best of my knowledge.

Wm. M. Raymond
 Wm. M. Raymond, President

Subscribed and sworn to before me this 27th day of June, 1962.

Bernice Bolt
 Notary Public

My commission expires
 December 10, 1962