

RECEIVED
KCC DISTRICT #2

JUN 27 2005

WICHITA, KS

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

RECEIVED

JUN 28 2005

KCC WICHITA

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 15-113-02057-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 11-4-07

Well Operator: E & E Oil (Owner / Company Name) KCC License #: 31448 (Operator's)

Address: Box 451 City: Canton

State: KANSAS Zip Code: 67428 Contact Phone: (620) 628-4858

Lease: Stucky Holloway Well #: 6 cell 620, 654-8140
Sec. 3 Twp. 18 S. R. 1 East West

NW - NE - NE Spot Location / QQQQ County: McPherson

330 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

~~660-990~~ Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)
KCC-SKA-630-05-Per RBDMS + Well Record.

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 202 Cemented with: 135 Sacks

Production Casing Size: 5 1/2" Set at: 2776 Cemented with: 75 Sacks

List (ALL) Perforations and Bridgeplug Sets: 2720-2732

Elevation: 1387 (G.L. / K.B.) T.D.: _____ P.B.T.D.: _____ Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed):
sand bottom to 2700' dumped 5 sacks cement plug as required by state

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Lawrence Everhart

Phone: (620) 654-8140

Address: Box 451 City / State: Canton, Kansas

Plugging Contractor: Mike's Testing & Salvage, Inc KCC License #: 30904 31529
~~Kelso Casing Pulling, Inc.~~ (Contractor's)

Address: Box 209467 Chase, Kansas Phone: (620) 938-2943 2537

Proposed Date and Hour of Plugging (if known?): as soon as possible

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 6-24-05 Authorized Operator / Agent: Lawrence D. Everhart (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

4/106

9/05

RECEIVED
KCC DISTRICT #2

JUN 27 2005

WICHITA, KS

WELL RECORD

STUCKY-HOLLOWAY WELL NO. 6

RECEIVED

JUN 28 2005

KCC WICHITA

Location: NW/4 NE/4 NE/4
Sec. 3-18S-1W
McPherson County
Kansas

Operator: Glickman Oil Company
702 South St. Francis
Wichita, Kansas

Contractor: J. A. Melland, Rotary Drilling Contractor
1111 North Main Street
Hutchinson, Kansas

Casing Record: 8-5/8" OD casing set and cemented at 202' with 135 sacks of
cement and 2% calcium chloride. Cement circulated.
5-1/2" OD casing set and cemented at 2776' with 75 sacks of
cement.

<u>FORMATION</u>	<u>LOG</u>
Surface soil & clay	35
Sand	75
Shale & shells	185
Gypsum, shale & shells	202
Gypsum, lime & shale	220
Lime & shale	400
Lime	800
Shale & lime	960
Shale & shells	1205
Shale & lime	1600
Lime	1635
Lime & shale	1920
Sandy shale	2022
Shale & lime	2115
Lime & shale	2200
Lime	2500
Shale & lime	2696
Mississippi Lime	2777
ROTARY TOTAL DEPTH	2973

RECEIVED

NOV 25 1957

GLICKMAN COMPANY

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Everhart, Lawrence D. dba E & E Oil
PO Box 451
Canton, KS 67428

June 30, 2005

Re: STUCKY-HOLLOWAY #6
API 15-113-02057-00-00
NWNENE 3-18S-1W, 330 FNL 990 FEL
MCPHERSON COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,


David P. Williams
Production Supervisor

District: #2
3450 N. Rock Road, Suite 601
Wichita, KS 67226
(316) 630-4000