

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 45-37
LOCATION SE SE NW
SEC. 17 TWP. 7 RGE. 22

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Federal Land Bank

Operator Lion Oil Co Address Pratt Kans

Field _____ County Graham

Total Depth 3861 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 214' circulated with cement - 5 1/2" at 3850 with 200
sax cement behind - Lane Wells plugs to 3575'. Top Perf 3560'.
Filled with sand to 3555'. set 4 sax cement with dump bailer,
pulled 1500' 5 1/2", filled with mud to 210'. set rock and 15
sax cement, mud to 35', set rock and 10 sax cement to bottom
cellar.

PLUGGING
FILE SEC 17 T 7 R 22
BOOK PAGE 15 OF 38
RECEIVED
STATE CORPORATION COMMISSION
OCT 10 1952
OCT 10 1952
CONSERVATION DIVISION
Wichita, Kansas

Edmund Petty
District Conservation Agent

Date 10-5-52