

KANSAS

FORM CP-3
Rev. 10-8-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-065-21,5370000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Delbert Worcester

Complete Address R. R. Hill City, Kansas 67642

Lease Name A & D Worcester "B" Well No. #2

Location SW NE SW Sec. 14 Twp. 7 Rge. 22 (East) (West)

County Graham Total Depth 3775'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Hellberg Oil Company

Address Box 32, Morland, Kansas 67650 License No. _____

Operation Completed: Hour: 2:45AM Day: 13th Month: Dec. Year: 19 81

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8"-206' s.p. cuc. w/140 sacks common-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 980' w/70 sacks cement

2nd plug @ 210' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement

Circulate with 10 sacks of cement in rat hole.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

DATE 1-21-81
INV. NO. 9026

STATE CORPORATION COMMISSION
RECEIVED
DEC 21 1981

12/21/81