



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 9 1974

CONSERVATION DIVISION
Wichita, Kansas

12-9-74

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. John Wright of Continental Oil Company has this

date requested permission to plug the following described well:

Mr. Wright guarantees payment of the plugging fee.

Operator's full Name: Continental Oil Company,

Complete Address: 3535 NW 58th Street, Oklahoma City, Oklahoma.

Lease Name: Adell L-KC Unit Well No. 205

Location: SW-SW-NW Sec. 12 Twp. 6 Rge. (E)(W) 27

County: Sheridan Total Depth 3870' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Wright was instructed to plug the well as follows:

2 1/4" --- 103/4" Surface casing, cement circulated with 300 Sx.
3869' --- 7" OD Production casing cemented on bottom with 300 Sx. Well
plugged back to 3850'. Top of perforations @ ~~38~~ 3638'.

Push plug to 3630', sand back to 3590' and set 6' Sx. cement with dump
bailer. Pull 7" casing and squeeze well with 5 sacks hulls, 45 sacks
gel and 190 Cu. Ft. cement, staged.

Very truly yours,

Conservation Division Agent