

State of Kansas



15-163-30172-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 27 1966
JUN 27 1966
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Cook of Abercrombie Drlg. Co. has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Alyward Drilling Co.

Complete Address: 909 First National Bank Bldg. Wichita, Kansas

Lease Name: Grover "B" Well No. 1

Location: E/2 NE NW Sec. 22 Twp. 7 Rge. 19 (E)(W) X

County Rooks Total Depth 3792 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 500 Ft. and
displace 20 sax cement thru drill pipe. Heavy mud to 240 Ft. set
cementing plug and displace 15 sax cement thru drill pipe. Heavy
mud to 40 Ft. set cementing plug, 1/3 sax hulls and 8 sax cement
to base of celler. Plug rat hole with 2 sax cement.

Very truly yours,

Leo Massey
Conservation Division Agent