

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 18 1965
OCT 18, 1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Leo Lindenmuth of Chief Drlg. Co. Inc., has this date requested permission to plug the following described well:

Mr. Lindenmuth guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Company, Incorporated,

Complete Address: Box #797, Great Bend, Kansas.

Lease Name: Worchester Well No. 1

Location: CE/2-E/2-SW/4 Sec. 17 Twp. 7 Rge. (E)(W) 22

County Graham Total Depth 3762 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lindenmuth was instructed to plug the well as follows:

225' 8 5/8" Surface pipe. Pumped in 200 Sx. cement, did not circulate. Cement found 50' from surface. Ran crushed rock around surface pipe to bottom of cellar.

Circulate hole with heavy mud, set plug @ 540' and 20 Sx. cement.

" " 210' and 20 Sx. cement.

" " 40' with 1/2 sk. hulls & 10 Sx. cement.

Very truly yours,

H. L. Nichols
Conservation Division Agent