

4-032306

5-19

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-163-22,810 -00-00

SW SE SE /4 SEC. 30, 07, 19 W
400 feet from S section line
790 feet from E section line

Operator license# 5352

Lease: Biery Well # B-2

Operator: Baird Oil Company, Inc.

County: Rooks

Address: P.O. Box 428
Logan, Kansas 67646

Well total depth 3406 ^{110.70} feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 248 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 19 Month: May Year: 1998

Plugging proposal received from: Jim Baird

Company: Baird Oil Company, Inc. Phone: -

Were: Order 250 sxs 60/40 pozmix - 10% gel - 500# hulls.

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
JUN 10 1998
10:01 AM
C-163-22810-00-00
Sums 1998

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All , Part , None

Completed: Hour: 9:30 A.M., Day: 19 Month: May Year: 1998

Actual plugging report: 8 5/8" set at 248' w/190 sxs cwc. 5 1/2" set at 3406' w/125 sxs.
Prod.perfs 3326' - 3331'. D.V. Tool at 1490' w/350 sxs cwc. Squeezed 5 1/2" with 240
sxs cement blend with 500# hulls mixed in to Max. P.S.I. 1000#. Held. Tested 8 5/8" with
zero sxs to 700#. Cement at surface. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING Elevation: _____ GL

I did / did not observe the plugging.

Carl Goodrow
(agent)

INVOICED
DATE JUN 08 1998
INV. NO. 50677