

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22328-00-00
Spot: CNWSWSE Sec/Twnshp/Rge: 13-7S-21W
990 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: HAMEL Well Number: 1
County: GRAHAM Total Vertical Depth: 3630 feet

Operator License No.: 30076
Op Name: A & A PRODUCTION
Address: PO BOX 100
HILL CITY, KS 67642

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 256
Production: Size 4.5 feet: 3620
Liner: Size feet:

\$117.98

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/02/2001 2:00 PM
Plug Co. License No.: 30076 Plug Co. Name: A & A PRODUCTION
Proposal Rcvd. from: ANDY ANDERSON Company: A & A PRODUCTION Phone: (785) 421-6266

Proposed Plugging Method: Order 8 yards Redi-Mix - 6 sxs common cement with sand/yard.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/02/2001 3:30 PM KCC Agent: CARL GOODROW

Actual Plugging Report:
8 5/8" set at 256' w/165 sxs. 4 1/2" set 3620' w/175 sxs.
Two stage to surface cement in braden head - could not pull casing.
Prod. Perfs 3313' - 3371'.
Casing leak in C.H. - sand filled up to C.H. - shot off tubing.
Filled casing with 5 yards Redi-Mix.
Plug complete.

INVOICED
DATE 5-29-01
INV. NO. 2001061839

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 22 2001
CONSERVATION DIVISION
5/22/01

Remarks:
Plugged through: CSG

District: 04 Signed Carl Goodrow
(TECHNICIAN)

MAY 09 2001

K & E PETROLEUM, INC.

13-7-21W

100 S. MAIN, #300

#1 HAMEL

NW SW SE


WICHITA, KS. 67202

CONTR ABERCROMBIE DRILLING

CTY GRAHAM

GEOL TIM PRIEST

FIELD WC(1/2 W OF LESAGE,
SEP BY DRY HOLES)



ELV 2108 KB SPD 10/9/86 CARD ISSUED 12/11/86

IP 95 BO & 10 BWPD

2103 GL DRLG COMP 10/17/86

SHAW(TOP) 3313-3316
LKC 3366-3371

LOG	Tops	Depth/Datum
ANH	1696+	412
B/ANH	1728+	380
TOP	3081-	973
HEEB	3289-	1181
TOR	3313-	1205
LANS	3328-	1220
MUN CR	3443-	1335
BKC	3526-	1418
ARB	3567-	1459
GRAN	3613-	1505
RTD	3620-	1512
LTD	3621-	1513

8 5/8 " 256 / 165 SX, 4 1/2 " 3619 / 175 SX, PORT COLLAR AT 1619

DST (1) 3233-3255 (SHAW) / 45-60-45-60, REC 567' W, 31' M (CHL 45,580 PPM), SIP 877-877#, FP 19-169 / 169-300#, HP 1621-1621#

DST (2) 3285-3322 (TOR) / 45-60-45-60, REC 125' OIL (GR 36%), 30' OCM (20% OIL, 80% M), SIP 1100-1100#, FP 38-56 / 56-75#, HP 1658-1639#

DST (3) 3320-3345 (LKC A) / 45-60-75-90, REC 30' WM (50% W), 120' W (CHL 72,000 PPM), SIP 1164-1144#, FP 40-50 / 71-101#, HP 1720-1700#

DST (4) 3352-3380 (LKC B) / 45-60-45-60, 180' GIP, REC 1200' CLEAN GSY OIL (GR 39%), 60" GSY OCM (30% OIL, 20% G, 50% M), SIP 1005-986#, FP 71-325 / 376-497#, HP 1720-1710#

DST (5) 3378-3415 (LKC D.E.F) / 45-60-45-60, REC 10' OIL, 160' OCWM (5% OIL, 40% W, 55% M), 480' OCW (3% OIL), 720' W, W / SCUM OIL (CHL 66,000 PPM), SIP 856-856#, FP 132-517 / 557-577#, HP 1740-1720#

COPYRIGHT 1985
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)

13-7-21W