

To: **6 031344**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3-15 187 R
API NUMBER 15- 065-22,404 0000

SW SE NE, SEC. 12, T 7 S, R 21 W/EK
2970 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # _____
State of Kansas
Operator: _____
Name & Address KCC
Fee Fund Plugging

Lease Name Roberts Well # D 1
County Graham
Well Total Depth 3700 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 247

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____ Drill out to plug w/fee funds.

Plugging Contractor Allied Cement License Number _____
Address Russell, Ks.

Company to plug at: Hour: _____ PM Day: 15 Month: Mar Year: 19 90

Plugging proposal received from Don Butcher
(company name) District #4 Supervisor (phone) _____

were: 8 5/8" set at 247 cwc. Order 600 sks 65/35 poz 8% gel 500# hulls.

Allied Cement Co. Leo Tank Service. Order 2 7/8" work string, 8 5/8" bit, 6 1/4" bit,
Homaco mud pump and swivel.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 7:00PM Day: 15 Month: Mar Year: 19 90

ACTUAL PLUGGING REPORT Wash down hole to anhydrite circulate and condition
hole w/good circulation. Mix and pump through tubing 250 sks cement blend w/good
circulation. Lay down 35 joints 2 7/8" tubing, Mix and pump 200 sks cement blend to
surface, lay down rest of tubing and drill collars. Fill displacement w/35 sks cement blend
for total of 485 sks cement blend w/500# hulls mixed in. Plug complete.

Remarks: _____
(If additional description of well is necessary, use BACK of this form.)

I (did / did not) observe this plug on 8/2/90
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow