

4 060100

6-22 ~~15-165~~ 15-065-22576-00.0

To
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065-22576

NW NE NW, SEC. 12, T 7 S, R 21 WXX

4950 feet from S section line

3690 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Lease Name Grif Roberts Well # "B" 1

Operator: Ritchie Exploration, Inc.

County Graham 118.95

Name & Address 125 N. Market, Suite #1000

Well Total Depth 3660 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 215

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XXXX

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling License Number 6033

Address Wichita, KS

Company to plug at: Hour: 4:15AM Day: 22 Month: June Year: 19 90

Plugging proposal received from Lloyd Delett

(company name) Murfin Drilling Co. (phone) _____

were: Order 190 sxs. 60/40 pos 6% gel 1/4# flocel per sx.

Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by Herb Deines
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XXXXXXXXXX

Operations Completed: Hour: 4:15AM Day: 22 Month: June Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 1725' with 25 sxs. Anhydrite 1707-1739'

2nd plug at 960' with 100 sxs. Dakota 660-960'

3rd plug at 265' with 40 sxs. Surface pipe to 215'

4th plug at 40' with 10 sxs.

rathole with 15 sxs.

RECEIVED
STATE CORPORATION COMMISSION

JUL 11 1990

Remarks: Allied Cementing CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED
XXXXXX (Total) observe this plugging.

DATE 7-17-90

Signed Herb Deines 7-11-90
(TECHNICIAN)

INV. NO. 28615

Herb Deines