

4-060841

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

2-21

API Number: 15-065-22,765 -06-00

SE SW SW /4 SEC. 17, 07 S, 22 W
330 feet from S section line
4290 feet from E section line

Operator license# 5123 Lease: Fountain G Well # 1

Operator: Pickrell Drilling Company, Inc. County: Graham

Address: 110 N. Market - Suite #205
Wichita, Kansas 67202
Well total depth 3960 128.70 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 229 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Co Tools License#

Address:

Company to plug at: Hour: 9:30 P.M. Day: 21 Month: February Year: 1996

Plugging proposal received from: Doyle Folkerts

Company: Pickrell Drilling Company, Inc. Phone: 316-262-8427

Were: Order 190 sxs 60/40 posmix - 6% gel with 1/4# floseal per sack.
Space all plugs with heavy drilling mud through drill pipe.

RECEIVED
KANSAS CORP COM
1996 FEB 29 A 11:16


Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 11:30P.M. Day: 21 Month: February Year: 1996

Actual plugging report:
1st. Plug at 1950' w/25 sxs. - Anhydrite to 1932' - 1957'.
2nd. Plug at 1200 w/100 sxs. - Dakota 880' - 1180'.
3rd. Plug at 280' w/40 sxs. - Surface pipe to 229'.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES, CALC, NO X Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: 2330 GL

I did/did not [X] observe the plugging.


(agent)
DK

INVOICED
DATE MAR 05 1996
INV. NO. 44949