

12-21

4-020041

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-065-22,732-00-00

SE SW SW /4 SEC. 30, 07 S, 21 W  
330 feet from S section line  
4290 feet from E section line

Operator license# 4767

Lease: Claude Kenyon Tr. Well # 1

Operator: Ritchie Exploration, Inc.

County: Graham

Address: 125 N. Market,  
Suite 1000  
Wichita, Kansas 67202

Well total depth 3740 feet 121.55  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 1/2 Inch @ 216 feet

Aband. oil well \_\_, Gas well \_\_, Input well \_\_, SWD \_\_, D & A X

Plugging contractor: Murfin Drilling Co. License# 30606

Address: 250 N. Water, Suite 300, Wichita, Kansas 67202

Company to plug at: Hour: \_\_\_\_\_ Day: 21 Month: December Year: 1993

Plugging proposal received from: Lloyd Delett

Company: Murfin Drilling Co. Phone: 316-267-3241

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 1795 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1000 feet with 100 sacks

3rd plug @ 265 feet with 40 sacks

4th plug @ 40 feet with 10 sacks

Plugging Proposal Received by: Ken Kuhn

Plugging operations attended by agent? All[ ], Part[ ], None[ X ]

Completed: Hour: 3:00, Day: 21, Month: December, Year: 1993

Actual plugging report: Hole reported plugged as above.

Order 190 sx 60/40 pozmix w/ 6% gel and 1.9 sx celloflake or flowcel

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 27 1993  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Allied Cementing performed the cementing.

Condition of casing(in hole): GOOD X BAD \_\_\_\_\_ Anhy. plug: YES X NO \_\_\_\_\_

Bottom plug(in place): YES X, CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES X, NO \_\_\_\_\_

Plugged through TUBING \_\_\_\_\_, CASING X. Elevation: 2180 GL

I did not [ X ] observe the plugging.

*Ken Kuhn*  
(agent)

INVOICED  
DATE 12-30-93  
INV. NO. 39608  
12-21