

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22938-00-00
Spot: N2N2N2NE Sec/Twnshp/Rge: 35-7S-21W
5032 feet from S Section Line, 1320 feet from E Section Line
Lease/Unit Name: WASHINGTON Well Number: 1
County: GRAHAM Total Vertical Depth: 3555 feet

Operator License No.: 9449
Op Name: GREAT EASTERN ENERGY & DEV. CO
Address: 550 W. TEXAS STE 660
MIDLAND, TX 79702

Surface Casing Size: 8.625 feet: 221

\$115⁵⁴

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/14/2003 9:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: ED MCKENNA Company: GREAT EASTERN ENERGY & DEV. Phone: (785) 443-1420

Proposed Plugging Method: Order 225 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT STAAB Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 10/14/2003 10:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

1st. Plug at 3510' w/25 sxs.
2nd. Plug at 1670' w/25 sxs.
3rd. Plug at 871' w/100 sxs.
4th. Plug at 271' w/40 sxs.
5th. Plug at 40' w/10 sxs. 8 5/8" wiper plug.
Rathole with 15 sxs.
Mousehole with 10 sxs.

RECEIVED
OCT 23, 2003
OCT 23 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed [Signature]
(TECHNICIAN)

INVOICED

DATE 10-23-03
INV. NO. 2004060666

OCT 21 2003