

X

4-031684

\*D-24,782

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-065-22,316 -00 00

SE NW SE /4 SEC. 12, 07 S, 21 W  
1650 feet from S section line  
1650 feet from E section line

Operator license# 4767

Lease Warren well # 2

Operator: Ritchie Exploration, Inc.

County Graham

Address: 125 N. Market #1000  
Wichita, Kansas 67202

Well total depth 3696 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 225 feet

Aband. oil well \_\_, Gas well \_\_, Input well \_\_, SWD ~~XX~~, D & A \_\_

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 17 Month: April Year: 92

Plugging proposal received from: Pete

Company: Ritchie Exploration, Inc. Phone: \_\_\_\_\_

Were: Order 300 sx. 65/35 pozmix - 10% gel. - 500# hulls.  
D.V. tool @ 1728' cwc. w/450 sx.  
Pull rods and tubing - hole open to production perf's.

CONSERVATION DIVISION  
WICHITA, KS

JUN 28 2005

RECEIVED  
KANSAS CORPORATION COMMISSION

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 12:15 P.M., Day: 17, Month: April, Year: 92

Actual plugging report: 8 5/8" set @ 225' w/150 sx. 5 1/2" set @ 3618'  
1/200 sx. P.B.T.D. 3560'. Top perf. 3324'. Tested 8 5/8" annulus.  
blew out head - cement at surface. Packer stuck up @ 2500'. Mixed  
and pumped down tubing 50 sx. cement blend. Backed off of packer.  
pumped 100 sx. cement blend on packer. Laid down 1250' of tubing.  
pumped 100 sx. cement blend to circulate. Laid down tubing. Loaded hole  
1/25 sx. cement blend. Used total of 275 sx. in 5 1/2" casing.  
plug complete.

Rec'd  
5-11-92

Remarks: Condition of casing(in hole): GOOD X BAD Anhy. plug: YES 1728 NO  
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO  
Plugged through TUBING, CASING. Elevation: N/A GL

did [ X ] / did not [ ] observe the plugging. Carl Goodrow

MD

(agent)

4-031684

4-17

16  
R

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-065-22,316-00-00

SE NW SE /4 SEC. 12, 07 S, 21 W  
1650 feet from S section line  
1650 feet from E section line

Operator license# 4767

Lease Warren well # 2

Operator: Ritchie Exploration, Inc.

County Graham

Address: 125 N. Market  
#1000  
Wichita, Kansas 67202

Well total depth 3696 feet <sup>120.12</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 225 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 17 Month: April Year: 92

Plugging proposal received from: Pete

Company: Ritchie Exploration, Inc. Phone: \_\_\_\_\_

Were: Order 300 sx. 65/35 pozmix - 10% gel. - 500# hulls.  
D.V. tool @ 1728' cwc. w/450 sx.  
Pull rods and tubing - hole open to production perf's.

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 12:15P.M., Day: 17, Month: April, Year: 92

Actual plugging report: 8 5/8" set @ 225' w/150 sx. 5 1/2" set @ 3618'  
w/200 sx. P.B.T.D. 3560'. Top perf. 3324'. Tested 8 5/8" annulus.  
Blew out head - cement at surface. Packer stuck up @ 2500'. Mixed  
and pumped down tubing 50 sx. cement blend. Backed off of packer.  
Pumped 100 sx. cement blend on packer. Laid down 1250' of tubing.  
Pumped 100 sx. cement blend to circulate. Laid down tubing. Loaded hole  
w/25 sx. cement blend. Used total of 275 sx. in 5 1/2" casing.  
Plug complete.

Remarks: \_\_\_\_\_  
Condition of casing(in hole): GOOD  BAD  Any plug: YES 1728 NO   
Bottom plug(in place): YES , CALC , NO  Dakota plug: YES  NO   
Plugged through TUBING , CASING . Elevation: N/A

I did  / did not  observe the plugging.

Carl Goodrow

DATE 5-18-92

INV. NO. 35-260

(agent)

Form CP-2/3

RECEIVED  
MAY 11 1992  
CONSERVATION DIVISION  
WICHITA, KANSAS

5/11/92