

1-21

41 R

6 - 031651

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-21,491-00-00
NWSWNE /4 SEC. 16, 07 S, 22 W
3630 feet from S section line
2310 feet from E section line

Operator license# 9354

Lease Worcester well # F16-1

Operator: Central Energy Inc.

County Graham

Address: Box 47590
Wichita, Ks.

Well total depth 3895 feet ^{26.58}
Conductor Pipe: inch @ feet
Surface pipe 8 5/8 inch @ 275 feet

Aband. oil well xx, Gas well , Input well , SWD , D & A

Plugging contractor: Great Bend Csg Pullers License# 4635

Address: Great Bend, Ks.

Company to plug at: Hour: PM Day: 21 Month: Jan Year: 92

Plugging proposal received from: Gary Burke

Company: G.B.Csg.Pullers phone:

Were: Order sand and common cement. Pull pipe. Order 250 sks 65/35
10% gel. 500 lbs. hulls. B. J. Services.

STATE CORPORATION COMMISSION RECEIVED

FEB 14 1992
FEB 14 1992
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All [x], Part [], None []

Completed: Hour: 6:00PM, Day 21, Month January, Year: 92

Actual plugging: 8 5/8 at 275 w/150 sks. 5 1/2 at 3880 w/150 sks.
Top perf at 3600. Plugged bottom w/sand & 5 sks cement to 3500.
Pump in 5 1/2. Ran 2" tubing to 1950. Displaced 40 sks cement blend
to 1240. Laid down tubing to 1240. Displaced 20 sks cement blend to 800
Laid down tubing. Shot off 5 1/2. Loaded casing w/cement blend. Laid
down 5 1/2 casing to 300. Cir cement blend to surface. Laid down 5 1/2
casing. Topped off 8 5/8 into cel.

Remarks:
Condition of casing (in hole): GOOD x BAD Anhy. plug: YES x NO
Bottom plug (in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING x, CASING x Elevation: GL

INVOICED

DATE 2-17-92 did [x] / did not [] observe the plugging.

Carl Goodrow
Carl Goodrow (agent)

INV. NO. 34571