

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

RECEIVED

JUL 20 2005

Form CP-4 September 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Noble Petroleum, Inc.

Address: 3101 N. Rock Rd. Suite 125 Wichita, Ks. 67226

Phone: (316) 636-5155 Operator License #: 31389

Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: (Date)

by: Virgil Clothier (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: Bottom: T.D. (repeated three times)

API Number: 15-159-01784-00-00 Comp. 6-9-50

Lease Name: Dobrinski

Well Number: 1

Spot Location (OOQQ): 10 SE SW NE 2310 Feet from X North / South Section Line

1650 Feet from X East / West Section Line

Sec. 10 Twp. 18 S. R. 8 East X West

County: Rice KCC

Date Well Completed: 6-9-1950 RBEM 7-20-05

Plugging Commenced: 6-22-05 RBDMs

Plugging Completed: 6-23-05

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows show casing sizes 8-5/8" and 5-1/2" with depths.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from feet to feet each set.

Plugged off bottom with sand to 3000' and 5 sacks cement. Cut casing loose @1300', pulled up to 1125', pumped 35 sacks cement, 775', hole circulated clean, laid down 5-1/2" casing, ran 2" tubing to 775', pumped 35 sacks cement, pulled up to 250' and circulated 100 sacks. 60/40 pos, 4% gel. Plugging Complete

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529

Address: P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Noble Petroleum, Inc.

State of Kansas County: Rice ss.

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Handwritten Signature]

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 18th day of July, 2005

[Handwritten Signature] Notary Public

My Commission Expires:

NOTARY PUBLIC - State of Kansas IRENE HERZBERG My Appt. Exp. 2-24-05

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten mark]