

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED

JUL 20 2005

KCC WICHITA

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Noble Petroleum, Inc.

Address: 3101 N. Rock Rd. Suite 125 Wichita, Ks.

Phone: (316) 636-5155 Operator License #: 31389 67226

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: Virgil Clothier (KCC District Agent's Name)

Is ACO-1 filed? ☐ Yes ☐ No If not, is well log attached? ☐ Yes ☐ No

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top:	Bottom:	T.D.
_____	_____	_____
_____	_____	_____
_____	_____	_____

API Number: 15-159-06260-00-00

Lease Name: Dobrinski

Well Number: 4

Spot Location (OOQQ): SE NW NE

4290 4325 Feet from North / South Section Line

1650 1795 Feet from East / West Section Line

Sec. 10 Twp. 18 S. R. 8 East X West

County: Rice

Date Well Completed: 3-27-1953

Plugging Commenced: 6-24-05

Plugging Completed: 6-28-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)			
Formation	Content	From	To	Size	Put In Pulled Out
				8-5/8"	190' None
				5-1/2"	3296' None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 3100' and 5 sacks cement. Cut holes in casing @775' and 250'. Ran 2" tubing to 1125', pumped 30 bbls. water, couldn't break circulation. Pumped 20 sacks gel, 35 sacks cement w/150# hulls, pulled up to 775', pumped 35 cement & 100# hulls, pulled up to 250, mixed all cement, Didn't circulate. Cement @160', ran in 2" & circ. 25 sxs. Ran in 1" & circ. 40 sxs. up backside. 60/40 pos, 4% gel Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529

Address: P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Noble Petroleum, Inc.

State of Kansas County: Rice ss.

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) Mike Kelso

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 18th day of July, 20 05

Irene Herzberg
Notary Public

My Commission Expires:



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202