

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Murfin Drilling Company, Inc.
Address: 250 N. Water, Suite 300
Phone: (316) 267-3241 Operator License #: 30606
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) *(If SWD or ENHR)*
The plugging proposal was approved on: 5/25/05 (Date)
by: David Williams, Wichita Ks (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
3100-3234 Arbuckle Depth to Top: _____ Bottom: _____ T.D. _____
3234 Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 053-00776-00-00
Lease Name: Shonyo
Well Number: #9
Spot Location (QQQQ): W2 - W2 - SE -
1304 Feet from North / South Section Line
2373 Feet from East / West Section Line
Sec. 9 Twp. 17 S. R. 8 East West
County: Ellsworth
Date Well Completed: 6/51
Plugging Commenced: 06/23/05
Plugging Completed: 06/23/05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	Surface	304'	10"	316'	0
	Production	Surface	3100'	5"	3100'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Rig up Allied Cementing to P&A. Spot 1st plug @ 2210' broke circ. Spot 10 sx 60/40 Poz w/4% gel, 2nd plug @ 1100' 35 sx 60/40 Poz w/4% gel, 3rd plug @ 750' 35 sx 60/40 Poz w/4% gel, pull to 370' Circ top plug to surface 10 sx 60/40 Poz w/4% gel cmt @ surface. Hook on to 8 5/8 x 5 1/2 annulus. Pressure to 1000#, plugging complete at 4:20 pm 6/23/05 witnessed by Virgil Clothier w/KCC. Total cement used 155 sx. RDMOL.

Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606
Address: 250 N. Water, Suite 300 ; Wichita, KS 67202


Name of Party Responsible for Plugging Fees: Murfin Drilling Company, Inc.

State of Kansas County, Sedgwick, ss.

Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 250 N. Water, Suite 300; Wichita, KS 67202



and SWORN TO before me this 15th day of July, 20 05
Susan Brady My Commission Expires: 11-4-07
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
JUL 18 2005
KCC WICHITA