

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-163-22376-00-00

LEASE NAME Schoeller

WELL NUMBER 4

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 32 TWP. 7s RGE. 19W (E) or (W)

COUNTY Rooks

Date Well Completed         

Plugging Commenced 7-13-94

Plugging Completed 7-19-94

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Thunderbird Drilling, Inc.

ADDRESS P. O. Box 97 Ellinwood, KS 67526

PHONE# (316) 564-2577 OPERATORS LICENSE NO. 5131

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on          (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filled?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 3405'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	346'	none
				4 1/2	3397'	1038'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet each set.  
Sanded off bottom to 3250' & ran 4 sks cement. Shot @ 1768' & 1038', worked pipe free, pulled 2 joints. Mixed 80 sks w/300# hulls @ 1800. Pulled pipe up to 350', mixed 100 sks w/200# hulls & circulated to surface. Pulled rest of pipe, topped off with 10 sks. 60/40 poz 10% gel Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Thunderbird Drilling, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 26th day of July

Irene Herzberg  
Notary Public

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 27 1994  
7/27/94  
CONSERVATION DIVISION  
Wichita, Kansas

My Commission Expires:         

