


15-163-06342-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Rooks \_\_\_\_\_ County, Sec. 32 Twp. 7S Rge. 19 (~~W~~ W) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE SE NW

Lease Owner DEEP ROCK OIL CORPORATION

Lease Name Schoeller Well No. 1

Office Address Box #1051, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 6 19 51

Application for plugging filed April 11 19 51

Application for plugging approved April 10 19 51

Plugging commenced April 7 19 51

Plugging completed April 8 19 51

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes From Eldon Petty on April 7, 1951

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Arbuckle Depth to top 3370' Bottom 3405' Total Depth of Well 3405' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	134'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud from 3405' up to 400', put in wood and rock bridge at 400', cemented with 30 sacks cement. Put in heavy mud. Put in wood and rock bridge at 144'. Put in 10 sacks cement. Put in heavy mud. Set wood and rock bridge at 25'. Put in 10 sacks cement, filled to top of hole and in cellar.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Deep Rock Oil Corporation  
Address Box #429, Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Reno, ss.  
Jack Smith (employee of owner) or (~~owner~~ operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack Smith

Box #429, Hutchinson, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 18<sup>th</sup> day of April, 19 51

My commission expires 8-23-54  
Notary Public. Barbara Williams

23-5091-s 8-50-10M

PLUGGING  
FILE SEC 32T 7 R 19W  
BOOK PAGE 7X LINE 36

RECEIVED  
STATE CORPORATION COMMISSION

APR 19 1951

CONSERVATION DIVISION  
Wichita, Kansas

4-19-51

15-163-00342-0000

Shoeller #1  
NE SE NW  
Sec. 32-7-19W  
Rooks County, Kansas

Set 8-5/8" surface pipe at 134'.  
Cemented w/125 sacks cement.

Surface Clay & Gravel	0	150
Shale & Shells	150	575
Sand	575	680
Lime and Shale	680	1395
Hard Lime	1395	1470
Shale & Shells	1470	1660
Lime & Shale	1660	2065
Broken Lime	2065	2435
Lime & Shale	2435	3000
Broken Lime	3000	3176
Lime	3176	3338
Shale & Lime	3338	3370
Lime	3370	3405
Total Depth		3405'.

**PLUGGING**  
FILE SEC 32 T 7 R 19W  
BOOK PAGE 7 LINE 36

**RECEIVED**  
STATE CORPORATION COMMISSION  
MAY 25 1951  
CONSERVATION DIVISION  
Wichita, Kansas