

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-15684-00-01

Spot: SWNESE

Sec/Twnshp/Rge: 4-16S-12W

1650 feet from S Section Line,

990 feet from E Section Line

Lease Name: POLZIN C

Well #: 3

County: BARTON

Total Vertical Depth: 3459 feet

Operator License No.: 33069

PROD Size: 5.5 feet: 3303 35 SX CMT

Op Name: ENCORE OPERATING COMPANY

SURF Size: 8.625 feet: 154 75 SX CMT

Address: P. O. BOX 27710

DENVER, CO 80227

#112 42

Well Type: SWD

UIC Docket No: D03096.0

Date/Time to Plug: 07/14/2005 2:30 PM

Plug Co. License No.: 33346

Plug Co. Name: TR SERVICE AND RENTAL, INC.

Proposal Rcvd. from: ROLAND NYP

Company: ENCORE OPERATING COMPANY

Phone: (785) 425-7387

Proposed

Ordered 300 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging

Recovered 80 joints out of 104 joints - unable to get below 472'.

Method:

Pumped 40 bbls water with 1/2 bbl per minute pump in rate on 07/05/2005.

Plugging Proposal Received By: PAT STAAB

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 07/14/2005 4:30 PM

KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

RIH with 15 joints to 470' - pulled one joint.
RIH with tubing to 441'. Allied tied onto tubing and pumped 35 sxs cement to circulate cement to surface.
Pulled tubing and tied onto 5 1/2' casing - pumped 125 sxs 60/40 pozmix neat, followed with 110 sxs cement with 500# hulls mixed in.
Max. P.S.I. 500#. S.I.P. 150#.
Tied onto 8 5/8" - pumped 20 sxs cement. Blew hole in top of casing - backside standing full.

Top	Bot	Thru	Comments
3330	3459	OH	

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

[Signature]

(TECHNICIAN)

RECEIVED

JUL 20 2005

KCC WICHITA

INVOICED

DATE

7-20-05

INV. NO

2006060070

Form CP-2/3

JUL 15 2005

MAOICEP

PALMER OIL CO

#3

POLZIN

4-16-12W
SW NE SE

Contr.

BARTON

County

E 1847 Comm 1-8-47 Comp 1-25-47 IP 50 BOPD


Tops	Depth	Datum
ANBY	772	
HEEB	2935	
LANS	3025	
ARB	3300	
TD	3306	

Casing

8" 154

5" 3301

500' OIH/1/2 hr



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS