

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01744-00-00
Spot: SESESW Sec/Twnshp/Rge: 27-9S-20W
330 feet from S Section Line, 2310 feet from W Section Line
Lease Name: HINKHOUSE Well #: 12
County: ROOKS Total Vertical Depth: 3829 feet

Operator License No.: 32638
Op Name: NADEL AND GUSSMAN, LLC
Address: 15 E. 5TH, SUITE 3200
TULSA, OK 74103

CIBP Size: feet: 3790
PROD Size: 5.5 feet: 3829 125 SX CMT
SURF Size: 8.625 feet: 147 125 SX CMT

#124⁴⁴

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/01/2005 8:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JOHN "ART" ROLO Company: NADEL & GUSSMAN, LLC Phone: (785) 434-2916

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 10% gel with 900# hulls.
Tubing fish at 2400' with holes in casing.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/01/2005 12:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Ran tubing to 2200'.
Pumped 25 sxs down backside. Max. P.S.I. 300#.
Pumped 200 sxs 60/40 pozmix - 10% gel down tubing with 300# hulls - circulated cement.
Pulled tubing - pumped 200 sxs cement down 5 1/2" casing with 600# hulls.
S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3703			
3664	3686		
3605	3616		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Dennis L. Hamel
(TECHNICIAN)

RECEIVED

JUL 20 2005

KCC WICHITA

INVOICED

DATE 7.20.05

INV. NO. 2006060072

Form CP-2/3

JUL 07 2005

NADEL & GUSSMAN

#12

HINKHOUSE

22 27-9-20W
Arb SE SE SW

Contr.

ROCKS

County

E. 2282

Comm.

Comp.

8-19-49

IP

3000 BOPD

Tops	Depth	Datum
TOP	3283	-1001
HEFB	3190	-1208
LANS	3529	-1247
CONG	3774	-1492
SIMP	3812	-1530
ARB	3828	-1546
T.O.	3830	-1548

Casing

6" 148 SWB 41 BOPH
5" 3829

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

WICHITA