

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24629-00-00
Spot: SENWSE Sec/Twnshp/Rge: 4-16S-12W
1650 feet from S Section Line, 1750 feet from E Section Line
Lease Name: JOHN MILLER Well #: 2
County: BARTON Total Vertical Depth: 3350 feet

Operator License No.: 33069
Op Name: ENCORE OPERATING COMPANY
Address: P. O. BOX 27710
DENVER, CO 80227

PROD Size: 5.5 feet: 3346 175 SX CMT
SURF Size: 8.625 feet: 411 225 SX CMT

Handwritten: \$ 108⁸⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/14/2005 10:00 AM
Plug Co. License No.: 33346 Plug Co. Name: TR SERVICE AND RENTAL, INC.
Proposal Rcvd. from: ROLAND NYP Company: ENCORE OPERATING COMPANY Phone: (785) 425-7387

Proposed Plugging Method: Ordered 330 sxs 60/40 pozmix - 10% gel - 500# hulls.
Casing leaks. Fluid level 372'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/14/2005 12:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Alliance RIH with tubing to 2100'.
Allied rigged to tubing and pumped 100 sxs 60/40 pozmix with 300# hulls mixed in.
Pulled tubing to 1500'. Allied rigged to tubing and pumped 135 sxs cement with 200# hulls mixed in to circulate cement into pit.
Pulled tubing - rigged to 5 1/2" casing with a swedge and pumped 50 sxs 60/40 pozmix.
Max. P.S.I. 700#. S.I.P. 250#.
Rigged to 8 5/8" casing with a swedge and pumped 30 sxs 60/40 pozmix.
Max. P.S.I. 500#. S.I.P. 250#.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2889 | 3313 | | |

Remarks: ALLIED CEMENTING COMPANY-TICKET #16457.

Plugged through: TBG

District: 04

Signed _____

Handwritten signature

(TECHNICIAN)

RECEIVED
JUL 20 2005
KCC WICHITA

INVOICED

Form CP-2/3

DATE 7-20-05

NO. 2006060070

JUL 15 2005

0048 770
 WADICED

replacement card

MAXWELL OPERATING CO
 HAYS KS 67601

Property of Ks Corp Comm
 4-16S-12W
 100'W, C SE NW SE

#2 MILLER, JOHN

site: 7-3/4 N & 2 W OF ODIN KS
 cont: DISCOVERY DRILLING # 1
 prod: RON NELSON

city: BARTON
 field: BEAVER NORTH

API 15-008-24629

In date 04/08/97 spd date 04/18/97 drig comp 04/24/97 card issued 07/21/97 last revised 06/29/98

| | | |
|--|--|--|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| ELV: 1875 KB, 1867 GL LOG | IP status: |
|-----------------------------|--|
| tops.....depth/datum | OIL, P 10 BO & 425 BWPD, SHAW 2889-2968 OA, DOUG 2994-3000 , LKC 3077-3221 OA , ARB 3310-3313 , 05/25/97 |
| * DAK SD.....232 + 1643 | LANS.....3044 - 1169 |
| * CED HILL.....382 + 1483 | BKC.....3290 - 1415 |
| * B/CED HILL.....681 + 1194 | ARB REW.....3309 - 1434 |
| * ANH.....794 + 1081 | * ARB CLEAN.....3318 - 1443 |
| * B/ANH.....817 + 1058 | LTD.....3322 - 1447 |
| * TOP.....2663 - 788 | RTD.....3350 - 1475 |
| * KH.....2788 - 913 | * GORHAM SD-ABSENT |
| * OH.....2856 - 981 | * SAMPLE TOP |
| HEEB.....2944 - 1089 | INFO RELEASED: 6/29/98 - WAS OIL WELL - TIGHT HOLE |
| TOR.....2964 - 1089 | CSG: 8-5/8" 411.07 / 225 SX (ALT 1), 5-1/2" 3346.55 / 175 SX |
| DOUG SH.....2976 - 1101 | |
| BR LM.....3034 - 1159 | |

COPYRIGHT 1988
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

(over)

MAXWELL OPERATING CO
 HAYS KS 67601

Property of Ks Corp Comm
 4-16S-12W
 100'W, C SE NW SE

#2 MILLER, JOHN

COMMENT: MIRT 4/17/97

SHOWS: 3178-3188 (LANS 140 LM, V SLI ODOR, NSFO, SCAT STN, MSTLY BARREN), 3232-3230 (LANS 180 LM, FR OIL ODOR, FEW PCS SCAT STN, NSFO)

NO CORES

DST (1) 2887-2920 (TOP), / 30-30-30-30, REC 15' SLI OCM (5% OIL, 95% M), 60' MW (60% W, 40% M) ISIP 696# FSIP 667# IFF 17# -38# FFP 40# -51# IHP 1380# FHP 1370# BHT 97'

DST (2) 2974-3010 (DOUG SD), / 45-45-45-45, 30' GIP, REC 30' SLI OILY WCM (5% OIL, 10% W, 85% M), 80' MW (60% W, 40% M) ISIP 745# FSIP 680# IFF 23# -46# FFP 49# -63# IHP 1462# FHP 1432# BHT 101'

DST (3) 3063-3143 (LANS C-F), / 45-45-45-45, 30' GIP, REC 40' OIL SPKD M (3% OIL, 97% M) ISIP 134# FSIP 235# IFF 25# -32# FFP 33# -38# IHP 1540# FHP 1542# BHT 100'

DST (4) 3288-3322 (ARB CLEAN), / 30-45-30-45, REC 2300' SW, W/OIL SPTS ON TOP ISIP 1024# FSIP 1043# IFF 420# -814# FFP 859# -890# IHP 1667# FHP 1631# BHT 116'

TRGT ZN: LKC (OIL), PTD 3400 (ARB), MICT - CO, PF (ARB REW) 3310-3313, W / 4 SPF, AC 200 GAL (15% MA), SO, PF (LKC) 3183-3184, 3217-3221, W / 2 SPF, AC 750 GAL (15% NE), COMMUNICATED, SO, PF (LKC) 3120-3123, W / 2 SPF, AC 500 GAL (15% NE), SO, PF (LKC) 3077-3080, W / 2 SPF, AC 500 GAL (15% NE), SO, PF (DOUG SD) 2994-3000, W / 2 SPF, AC 500 GAL (15% INS), SO, PF (TOR) 2985-2988, W / 2 SPF, AC 250 GAL (15% NE), PF (TOP) 2889-2891, 2911-2915, W / 2 SPF, AC 500 GAL (15% NE), SET 2-7/8" TBG AT 3300, NO PKR, POP, IFF 10 BO & 425 BWPD (GR 35), DOFP 5/25/97, COMMINGLED