

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-03154-00-00
Spot: NENENW Sec/Twnshp/Rge: 24-10S-20W
4950 feet from S Section Line, 2970 feet from E Section Line
Lease Name: SUTOR WEST Well #: 1
County: ROOKS Total Vertical Depth: 3721 feet

Operator License No.: 6931
Op Name: BOWMAN OIL COMPANY, A GENERAL
Address: 805 CODELL RD.
CODELL, KS 67663

PROD Size: 5.5 feet: 3718 w/150 sxs cmt
SURF Size: 8.625 feet: 285 w/250 sxs cmt

#120⁹³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/20/2005 9:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: DON BOWMAN Company: BOWMAN OIL COMPANY Phone: (785) 434-2286

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 10% gel - 300# hulls - 18 sxs gel.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/20/2005 12:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Perfs:

RIH with tubing to 2700'.
Mixed and pumped 18 sxs gel, followed with 40 sxs cement with 300# hulls mixed in cement.
Pulled up to 1700' - spotted 25 sxs cement.
Pulled up to 930' - circulated cement with 80 sxs.
POOH. Swaged onto 5 1/2" and topped with 50 sxs cement.
Annulus full of cement.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Dennis L. Hamel
(TECHNICIAN)

RECEIVED

JUL 20 2005

KCC WICHITA

INVOICED

DATE 7.20.05
INV. NO. 2006060667

Form CP-2/3

JUN 02 2005

C-G DRILLING & WOOD RIVER #1

OUTOP

21 9/10-20..

NE NE NW

INDEXED

Contr. _____

County _____

E. 2167

Comm. _____

Comp. _____

1-27-50

IP _____

2799 BOPD

Tops	Depth	Datum
HEEB	3378	
TOR	3398	
LANS	3417	-1250
SIMP	3685	-1518
ARB	3713	-1546
T.D.	3721	-1554

Casing

8" 285 SWB 2 1/2 BOPH/8 HRS
5" 3718 ACID 50

BERLAND POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS