

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25061-00-00
Spot: NESWNW Sec/Twnshp/Rge: 20-11S-20W
1620 feet from N Section Line, 1140 feet from W Section Line
Lease Name: R DENNING Well #: 1
County: ELLIS Total Vertical Depth: 3894 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3890	0	175 SX CMT
SURF	8.625	234	0	165 SX CMT

#126⁵⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/25/2005 1:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered out 220 sxs A Con Cement and 500# hulls.
Port collar at 1655' - set with 200 sxs cement.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/25/2005 4:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Swaged onto 4 1/2" - mixed and pumped 200 sxs cement with 400# hulls.
Max. P.S.I. 500#. S.I.P. 300#.
Hooked up to the annulus and pumped 10 sxs cement.
S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3794	3797		
3673	3675		
3624	3626		

Remarks: ACID SERVICES, INC.

Plugged through: CSG

District: 04

Signed _____

Jay Pfeifer
(TECHNICIAN)

INVOICED

DATE 8-01-05
INV. NO. 2006060217

JUL 27 2005

RECEIVED
AUG 01 2005
KCC WICHITA

Form CP-2/3

MURFIN DRILLING CO
WICHITA KS 67202

replacement card
WILDCAT

20-11S-20W
1620' FNL & 1140' FWL, SEC

#1 DENNING, R.

site: 5-1/2 N & 9-1/2 W OF HYACINTH KS

cty: ELLIS

API 15-051-25061

contr: MURFIN DRILLING #8

field: WC (NICHOLSON NE DISC)

geol: RANDALL KILIAN

fr date 10/24/2000

spd date 11/09/2000

drig comp 11/18/2000

card issued 02/05/2001

last revised 08/02/2004

ELV: 2194 KB, 2189 GL LOG	
tops.....	depth/datum
ANH.....	1630 +564
B/ANH.....	1668 +526
NEVA.....	2716 -522
TOP.....	3238 -1044
HEEB.....	3450 -1256
TOR.....	3473 -1279
LANS.....	3488 -1294
LANS B.....	3508 -1314
LANS C.....	3526 -1332
LANS D.....	3545 -1351
LANS E.....	3557 -1363
LANS F.....	3564 -1370
LANS G.....	3582 -1388

IP status

OIL, P 31 BO & 0.2 BWPD, LKC 3624-3675 OA, ARB
3794-3797 , 12/30/2000

LANS H.....	3624 -1430
LANS I.....	3646 -1452
LANS J.....	3665 -1471
LANS K.....	3682 -1488
LANS L.....	3704 -1510
BKC.....	3714 -1520
SIMP DOL.....	3780 -1586
ARB.....	3791 -1597
PBTD.....	3865 -1671
RTD.....	3891 -1697
LTD.....	3892 -1698

COPYRIGHT 2004
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)

WILDCAT