

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-02059-00-00  
Spot: NWSWNE Sec/Twnshp/Rge: 19-11S-16W  
3630 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: POTTER Well #: 6  
County: ELLIS Total Vertical Depth: 3377 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3373	0	w/150 sxs cmt
SURF	8.625	1050	0	w/500 sxs cmt

\$109<sup>75</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/25/2005 1:00 PM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: CURT GABEL Company: BEREXCO, INC. Phone: (785) 625-6101

Proposed Plugging Method: 07/25/2005 - Ordered 80 sxs common with 200# hulls. Did not witness.  
07/26/2005 - Rained out.  
07/27/2005 - Ordered out 250 sxs 60/40 pozmix - 10% gel with 500# hulls.  
Arbuckle 3368' - 3370'.  
Ran tubing to 3358'. Allied pumped 80 sxs common.  
PTOH. Unable to pull casing.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/27/2005 12:30 PM KCC Agent: RICHARD WILLIAMS

**Actual Plugging Report:**

07/25/2005 - Ran tubing to 3358'.  
Allied pumped 80 sxs common with 200# hulls.  
Displaced to 3358'. PTOH. Shut down. Did not witness.  
07/26/2005 - Rained out.  
07/27/2005 - Perf Tech perforated at 1675' - 1075' - 650'. Top cement 2336'.  
Ran tubing to 1700'. Allied pumped 160 sxs 60/40 pozmix - 10% gel cwc. PTOH.  
Allied pumped 65 sxs cement - hole full - coming around 5 1/2" x 8 5/8".  
Shut in.

**Perfs:**

Top	Bot	Thru	Comments
3373	3377	OH	
2808	3144		

RECEIVED  
AUG 03 2005  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

*Richard Williams*

(TECHNICIAN)

INVOICED

DATE

8-3-05

INV. NO

2006060227

Form CP-2/3

AUG 01 2005

WICHITA

OKMAR OIL

#6 POTTER

19-11-16W  
NW SW NE

Contr. GARVEY DRLG

ELLIS County


E 1864 Comm. Comp. 11-4-55 IP 25 BOPD

Tops	Depth	Datum
ANI	1040	824
TOP	2775	-911
HEEB	3012	-1148
LANS	3057	-1193
ARB	3372	-1508
TD	3377	-1513

Casing  
10" 620  
8" 1050  
5" 3373

DST 2800-15/60", 2250' MDY  
SW,  
CO 3377; 25 BOPD, 75% WTR

BEMIS SHUTTS POOL



INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS