

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22118-00-01
Spot: NWSESE Sec/Twnshp/Rge: 27-15S-21W
990 feet from S Section Line, 990 feet from E Section Line
Lease Name: JL LAND A Well #: 1
County: TREGO Total Vertical Depth: 4375 feet

Operator License No.: 6113
Op Name: LANDMARK RESOURCES, INC.
Address: 1616 S. VOSS, SUITE 150
HOUSTON, TX 77056

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4371	0	w/110 sxs cmt
SURF	8.625	292	0	w/165 sxs cmt

#142¹⁹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/13/2005 1:30 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: CHUCK SCHMIDT Company: LANDMARK RESOURCES INC. Phone: (713) 243-8550

Proposed Plugging Method: Ordered 205 sxs 60/40 pozmix - 10% gel - 500# hulls - 23 sxs gel.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/13/2005 4:30 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

DV tool at 1684' w/450 sxs cement.
Tied to 5 1/2" casing - pumped 38 sxs cement with 200# hulls, followed with 23 sxs gel with 300# hulls.
Squeezed 5 1/2' casing w/127 sxs cement.
Max. P.S.I. 600#. S.I.P. 300#.
Tied to 8 5/8" x 5 1/2" annulus - pressured to 375# P.S.I. - took no cement.
Total of 165 sxs 60/40 pozmix - 10% gel - 23 sxs gel and 500# hulls.

Perfs:

RECEIVED
AUG 03 2005
KCC WICHITA

Remarks: SWIFT SERVICES, INC. HD TANK SERVICE-WATER.

Plugged through: CSG

District: 04

Signed

Roger Moses
(TECHNICIAN)

INVOICED

DATE

8-3-05

INV. NO

2006060228

Form CP-2/3

JUL 29 2005

CHARTER PRODUCTION CO
WICHITA KS 67202

27-15S-21W
50'N, C NW SE SE

1 J & L LAND A OWWO

site: 5-1/4 N & 4-1/2 E OF BROWNELL KS
contr: CHEYENNE WELL SVC
incl: NONE

ay: TREC
field: WC (D) 50150
APR 15 1995 2218

tr date 01/02/95 : spd date 03/15/94 : drig comp 03/15/94 : card issued 01/02/95 : last revised 08/28/95 :

ELV: 2366 KB, 2357 GL LOG	
Tops.....	depth/datum
ANH.....	1682 + 684
B/ANH.....	1726 + 640
HEEB.....	3730 -1364
TOR.....	3758 -1392
LANS.....	3774 -1408
BKC.....	4034 -1668
PAW CHT.....	4111 -1745
LABETTE.....	4176 -1810
PAW SD.....	4197 -1831
PBTD.....	4214 -1848
CHER SD A.....	4222 -1856
CONG CHT.....	4283 -1917
MISS CHT.....	4294 -1928

IP status:
OIL, P 83 BOPD, NW, MARM 4198-4201, (NEW PAY) ,
03/17/94
MISS DOL4328 -1962
RTD OLD4375 -2009
INFO REL: 8/28/95 - WAS OIL WELL - TIGHT HOLE
NOTE: CORR & INFO REL 8/12/95 - ORIG FR IN NW SE
SE (CORR PER GEOL); ADDED OLD INFO
OLD INFO: OPERATOR WAS CHARTER PRODUCTION
CO, 1 J & L LAND A, SPD 12/14/92, 12/22/92 8-5/8" 292
/ 165 SX (ALT 2), 5-1/2" 4371 / 110 SX DV TOOL AT 1684
/ 450 SX OIL, P 40 BO & 40 BWPD, CHER 4221-4222,
01/19/93 (CARD ISSUED 05/10/93)
CONTR: DUKE DRILLING # 4
GEOL: TYLER SANDERS

COPYRIGHT 1985
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)

CHARTER PRODUCTION CO
WICHITA KS 67202

27-15S-21W
50'N, C NW SE SE

1 J & L LAND A OWWO

NO CORES

DST (1) 4169-4210 (PAW), / 30-15-0-0, (1ST OP) SB OFF BTM BKT/23", 898' GIP, REC 452
CLEAN GSY OIL (20% G, 80% OIL), 129' OC GSY M (20% G, 20% OIL, 60% M), REMARK: NO SIP
RECORDED IFP 88# -226# BHT 121"

DST (2) 4214-4228 (CHER SD A), / 30-45-30-60, (1ST OP) SB TO BTM BKT/9", (2ND OP) WB
BLDG TO 5 INCH, 325' GIP, REC 539' TOTAL FL: 303' CLEAN GSY OIL (20% G, 80% OIL), 236'
SLI OCMW (3% OIL, 87% W, 10% M) ISIP 749# FSIP 739# IFP 49# -137# FFP 167# -226# BHT
123"

TRGT ZN: MRW, MISS, PTD 4275 (MISS), MICT - CO, PF (CHER SD A) 5/4221.5-4222.5, GSO,
NAT, SET 2-7/8" TBG AT 4253, NO PKR, POP, P 40 BO & 40 BWPD, 1/19/93

NEW INFO: FR 01/02/95, RE YORKED 03/15/94 DC 03/15/94

COMMENT: KCC API 15-195 22118-0001

MICT - CO, SET BP AT 4214, PF (PAW SD) 4198-4201, W / 2 SPF, GSO, NAT, SET 2-7/8" TBG AT
4253, NO PKR, POP, P 83 BOPD, NW, 3/17/94 (NEW PAY)