

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-02373-00-00  
Spot: SESENE Sec/Twnshp/Rge: 3-12S-17W  
2970 feet from S Section Line, 330 feet from E Section Line  
Lease Name: WINDHOLZ Well #: 1  
County: ELLIS Total Vertical Depth: 3645 feet

Operator License No.: 5163  
Op Name: WHITE HAWK OIL COMPANY, A GENE  
Address: PO BOX 3363  
TULSA, OK 74101

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3550		
PROD	5.5	3599	0	60 SX CMT
SURF	8.625	160	0	100 SX CMT

#118 46

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/28/2005 8:00 AM  
Plug Co. License No.: 33346 Plug Co. Name: TR SERVICE AND RENTAL, INC.  
Proposal Rcvd. from: ART ROLO Company: WHITE HAWK OIL COMPANY Phone: (785) 483-2827

Proposed Plugging Method: Ordered out 200 sxs 60/40 pozmix - 10% gel - 300# hulls - 12 sxs gel spacer.  
Well squeezed at 842' w/320 sxs.  
Tubing stuck at 3300'. TOF at 3125'.

Plugging Proposal Received By: DENNIS HAMEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/28/2005 12:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

TIH with tubing to 3100' - mixed and pumped 12 sxs gel followed with 40 sxs cement with 200# hulls.  
Pulled up to 1300' and circulated cement with 125 sxs cement and 100# hulls.  
POOH. Topped with 35 sxs cement.  
Annulus full.

Perfs:

Top	Bot	Thru	Comments
3356	3532		

RECEIVED  
AUG 03 2005  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

*Jay Pfeifer*  
(TECHNICIAN)

INVOICED  
DATE 8-03-05  
NO. 2006060237

Form CP-2/3

JUL 29 2005

MISSOURI OIL & GAS

21

W. F. HUBBARD

1773  
3

3-12-17W  
SE SE NE

Contr. SECTION 20 T. 20. S. 20. E.

ELLIS

County

W. 2111 Comm. 12-2-13

Comp. 3-25-14

IP

55 ROD & 1/2" WT

FTY TOT

Tops	Depth	Datum
ALL	1375	+ 306
HELLS	3237	- 1176
LOG	3327	- 1266
ABD	3506	- 1485
T.D.	3642	- 1621

Casing

8" 110  
5" 55.8

SWP 12 LOGS TO 2000


INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

DATE

WAGON