

4- 041407

8-10

199
P

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-21,584 0000
NE /4 SEC. 32, 07 S, 19 W
3630 feet from S section line
330 feet from E section line

Operator license# 5131 Lease Schoeller well # 3

Operator: Thunderbird Drilling, Inc. County Rooks

Address: P.O. Box 97 Well total depth 3402 feet 110.56
Ellinwood, Kansas 67526 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 332 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Thunderbird Drilling - Allied Cement License# 5131

Address: Ellinwood, Kansas 67526

Company to plug at: Hour: 8:00A.M. Day: 10 Month: August Year: 92

Plugging proposal received from: Maynard Weber

Company: Thunderbird Drilling, Inc. Phone: 316-564-2577

Were: 4 1/2" casing set @ 3383' w/ 50 sx. cement. Perf. @ 3380' -
3402'. D.V. @ 1430' cwc. W.L.M. 3390'.
Ordered 225 sxs. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 400# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 1:00P.M., Day: 10, Month: August, Year: 92

Actual plugging report: 4 1/2" casing. Allied Cementing mixed and
pumped 225 sx. cement w/400# hulls. Max. P.S.I. 1000#. S.I.P. 1000#.
8 5/8" S.P. - filled to surface with cement.

RECEIVED
STATE CORPORATION COMMISSION
10/5/92
OCT 5 1992

Remarks: _____
Condition of casing(in hole): GOOD X BAD Any plug: YES X NO
Bottom plug(in place): YES X, CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did [X] / did not [] observe the plugging.

Dennis L. Hamel

INVOICED
DATE 10-8-92
INV. NO. 36387

(agent)
Form CP-2/3