

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-20439-00-00
Spot: W2E2E2 Sec/Twnshp/Rge: 28-4S-22W
2580 feet from N Section Line, 990 feet from E Section Line
Lease Name: SANSOM Well #: 5
County: NORTON Total Vertical Depth: 3796 feet

Operator License No.: 7076
Op Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

SURF Size: 8.625 feet: 227

#12337

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/14/2005 1:00 AM
Plug Co. License No.: 9292 Plug Co. Name: SCHECK, TIMOTHY DBA SCHECK OIL OPERATION
Proposal Rcvd. from: STAN LOVELADY Company: SCHECK, TIMOTHY DBA SCHECK Phone: (785) 324-0687

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT STAAB Witness Type: NONE
Date/Time Plugging Completed: 07/14/2005 2:30 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:


1st. Plug at 3689' w/25 sxs.
2nd. Plug at 1907' w/25 sxs.
3rd. Plug at 1145' w/100 sxs.
4th. Plug at 277' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

RECEIVED

JUL 20 2005

KCC WICHITA

INVOICED

DATE 7-20-05

INV. NO. 2006060066

Form CP-2/3

JUL 15 2005