

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-173-01327-00-01
Spot: S2S2SW Sec/Twnshp/Rge: 24-27S-2W
330 feet from S Section Line, 3860 feet from E Section Line
Lease Name: BETZEN Well #: 2
County: SEDGWICK Total Vertical Depth: 3826 feet

Operator License No.: 5822
Op Name: VAL ENERGY, INC.
Address: PO BOX 116
WICHITA, KS 67201

CIBP Size: 0 feet: 3398
CIBP Size: feet: 3434
L1 Size: 4.5 feet: 3798
PROD Size: 5.5 feet: 3520 100 SX CMT
SURF Size: 8.625 feet: 412 275 SX CMT

#124³⁵

Well Type: SWD UIC Docket No: D21741.0 Date/Time to Plug: 06/10/2005 8:00 AM
Plug Co. License No.: 31539 Plug Co. Name: SAMS WELL SERVICE, INC.
Proposal Rcvd. from: TODD ALLAM Company: VAL ENERGY Phone: (316) 263-6688

Proposed Plugging Method: ALL PERFS SQUEEZED OFF SET 5-1/2 CIBP @ 3434 TO SHUT OFF LINER, SET 5-1/2 CIBP @ 3398 & TOP W/2 SX CMT, PERF @ 500' RUN TUBING AND CIRCULATE CMT TO SURFACE INSIDE AND OUT. NO CASING PULLED.

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/13/2005 10:00 AM KCC Agent: DAVE WERTZ

Actual Plugging Report:

Squeezed Mississippi perforations with cement; set CIBP at 3434'; set CIBP at 3398'; and spttd 2 sacks of cement with bailer. Shot holes in 5-1/2" tubing at 500' and ran tubing to 500' inside the 5-1/2" tubing. Circulated cement to surface and tied onto backside; circulated cement to surface.

United #6312

60/40 posmix with 4% gel

Perfs:

Top	Bot	Thru	Comments
3437	3804		
3420	3428		

**RECEIVED
KCC DISTRICT #2
JUL 18 2005
WICHITA, KS**

Remarks: DUAL COMPLETION

Plugged through: TBG

District: 02
**RECEIVED
KANSAS CORPORATION COMMISSION
JUL 19 2005
CONSERVATION DIVISION
WICHITA, KS**

Signed Paul Wertz (TECHNICIAN)
INVOICED
DATE 7-19-05
WV. NO. 2006060064