

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-21138-00-00  
Spot: E2NESE Sec/Twnshp/Rge: 26-17S-10W  
1910 feet from S Section Line, 420 feet from E Section Line  
Lease Name: WOYDZIAK Well #: 1-26  
County: ELLSWORTH Total Vertical Depth: 3300 feet

Operator License No.: 3882  
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN  
Address: 1670 BROADWAY #3300  
DENVER, CO 80202

SURF Size: 8.625 feet: 299 175 SX CMT

*\$ 107<sup>25</sup>*

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/04/2005 8:00 AM  
Plug Co. License No.: 33323 Plug Co. Name: PETROMARK DRILLING, LLC  
Proposal Rcvd. from: TOM LARSON Company: \_\_\_\_\_ Phone: (620) 793-2168

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE  
Date/Time Plugging Completed: 06/04/2005 5:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

Pumped 35 sacks of cement through drill pipe at 3248'. Pulled to 1250' and pumped 35 sacks of cement. Pulled to 950' and pumped 35 sacks of cement. Pulled to 350' and pumped 35 sacks of cement. Pulled to 60' and circulated 25 sacks of cement to surface. Pumped 15 sacks of cement in rathole.

Allied Cement #18388

60/40 posmix with 4% gel

RECEIVED  
KCC DISTRICT #2  
JUL 13 2005  
WICHITA, KS

Remarks:

Plugged through: DP

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

**INVOICED**  
DATE 8-01-05  
INV. NO. 2006060215

RECEIVED  
AUG 01 2005  
KCC WICHITA