

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-169-00638-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 30-15S-3W
351 feet from S Section Line, 5142 feet from E Section Line
Lease Name: OSTENBERG Well #: 3
County: SALINE Total Vertical Depth: 3412 feet

Operator License No.: 6819
Op Name: SCOTT'S WELL SERVICE INC
Address: PO BOX 136
ROXBURY, KS 67476

PROD Size: 5.5 feet: 3412 65 SX CMT
SURF Size: 8.625 feet: 342 220 SX CMT

#110⁸⁹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/11/2005 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: Sand bottom to 3362' and cap with 5 sxs cement. Pull pipe and bridge at 400'. Bail water to 400'. Pump slurry mix from top to fill from 400' to surface.

Plugging Proposal Received By: GREG EVES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/11/2005 3:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

Perfs:

Sanded bottom to 3362' and capped with 5 sacks of cement. Pulled pipe and then set bridge at 400'. Bailed fluids out of hole to 400'. Dumped slurry mix from 410' to surface.

Recovered 697' of production pipe

Smokey Valley #011316

110 sacks total of 60/40 posmix with 4% gel
Slurry mix = 60 gals/sacks cement

RECEIVED
KCC DISTRICT #2
JUL 18 2005
WICHITA, KS

Remarks: PLUGGED THROUGH SURFACE PIPE

Plugged through: CSG

District: 02

Signed

Greg Eves

(TECHNICIAN)

INVOICED

DATE 8-01-05
IN. NO. 2006060224

RECEIVED

AUG 01 2005

KCC WICHITA

ca