

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-20408-00-00
Spot: S2NENE Sec/Twnshp/Rge: 9-32S-6W
4290 feet from S Section Line, 660 feet from E Section Line
Lease Name: HOSTETLER A Well #: 2
County: HARPER Total Vertical Depth: 5050 feet

Operator License No.: 30952
Op Name: NICHOLAS WATER SERVICE, INC.
Address: PO BOX 113
ZENDA, KS 67159

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	5050	1300	500 SX CMT
SURF	8.625	247		225 SX CMT

#164¹³

Well Type: SWD UIC Docket No: D19263.0 Date/Time to Plug: 07/08/2005 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Perf 4944' - 4954'; Sand to 4890' & 5 sxs; 1300' & 35 sxs; 700' & 35 sxs; circ 304'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 07/08/2005 2:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The perforations were sanded to 4890' and capped with 5 sacks of cement. Casing recovered from 3100' and pulled to 1300' where 35 sacks of cement was spotted. Pulled casing to 700' and spotted 35 sacks of cement. Pulled casing to 300' and circulated cement to surface.

United Cement #6275

60/40 posmix with 4% gel

Perfs:

Top	Bot	Thru	Comments
4944	4954		

RECEIVED
KCC DISTRICT #2
JUL 20 2005
WICHITA, KS

Remarks: INACTIVE LICENSE PLUGGING APPROVED BY LEGAL DEPT.

Plugged through: DP

District: 02

Signed 
(TECHNICIAN)

INVOICED
DATE 8-01-05
INV. NO. 2006060219

RECEIVED
AUG 01 2005
KCC WICHITA