

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-24222-00-00
Spot: NWNESW Sec/Twnshp/Rge: 17-30S-7E
2310 feet from S Section Line, 1650 feet from W Section Line
Lease Name: WFC Well #: 1
County: COWLEY Total Vertical Depth: 3305 feet

Operator License No.: 6723
Op Name: BAKER, DON DBA CAMIO OIL COMPA
Address: PO BOX 308
AUGUSTA, KS 67010

SURF Size: 8.625 feet: 302

\$107⁴¹

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/12/2005 5:00 PM
Plug Co. License No.: 32854 Plug Co. Name: GULICK DRILLING CO., INC.
Proposal Rcvd. from: RON GULICK Company: GULICK DRILLING CO., INC. Phone: (620) 583-3066

Proposed Plugging Method: 25 sxs Arb; 35 sxs @ 352'; 25 sxs @ 60'; and 15 sxs in rathole.

Plugging Proposal Received By: DAVE WERTZ WitnessType: NONE
Date/Time Plugging Completed: 07/12/2005 7:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perfs:

Ran drill pipe to 3287' and spotted 25 sacks of cement. Pulled drill pipe to 352' and spotted 35 sacks of cement. Pulled drill pipe to 60' and circulated to surface. Circulated 15 sacks of cement in rathole.

United Cement #6412

60/40 posmix with 4% gel.

RECEIVED
KCC DISTRICT #2
JUL 18 2005
WICHITA, KS

Remarks:

Plugged through: DP

District: 02

Signed _____

[Signature]
(TECHNICIAN)

INVOICED

RECEIVED

DATE

8-01-05

AUG 01 2005

NO

2006060210

KCC WICHITA