

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-169-20057-00-00  
Spot: SENWSW Sec/Twnshp/Rge: 30-15S-3W  
1499 feet from S Section Line, 4056 feet from E Section Line  
Lease Name: OSTENBERG Well #: 5  
County: SALINE Total Vertical Depth: 3425 feet

Operator License No.: 6819  
Op Name: SCOTT'S WELL SERVICE INC  
Address: PO BOX 136  
ROXBURY, KS 67476

PROD Size: 5.5 feet: 3425 175 SX CMT  
SURF Size: 8.625 feet: 360 250 SX CMT

*11131*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/06/2005 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MONTY ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Sand bottom to 3350' and cap with 5 sxs cement. Pull pipe and set bridge at 410'. Dump slurry mix from top to fill from  
Plugging 410' to surface.  
Method:

Plugging Proposal Received By: GREG EVES WitnessType: PARTIAL  
Date/Time Plugging Completed: 07/06/2005 11:30 AM KCC Agent: GREG EVES

**Actual Plugging Report:**

Sanded bottom to 3350' and capped with 5 sacks of cement. Pulled pipe and then set bridge at 410'. Bailed fluids out of hole to 410'. Dumped slurry mix from 410' to surface through surface pipe.

Smokey Valley Concrete #011256

110 sacks of 60/40 posmix with 4% gel  
Slurry mix = 110 sx cement & 660 gal water

**Perfs:**

Top	Bot	Thru	Comments
3411	3416		

**RECEIVED  
KCC DISTRICT #2  
JUL 15 2005  
WICHITA, KS**

Remarks: PLUGGED THROUGH SURFACE PIPE

Plugged through: CSG

District: 02

Signed Greg Eves

(TECHNICIAN)

**INVOICED**

DATE 8-01-05

INV. NO. 2006060224

**RECEIVED**

AUG 01 2005

**KCC WICHITA**