

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21424-00-00
Spot: N2N2SENV Sec/Twnshp/Rge: 32-32S-6W
1440 feet from N Section Line, 1980 feet from W Section Line
Lease Name: OSBORNE Well #: 1
County: HARPER Total Vertical Depth: 5050 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 NORTH MARKET, STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	5047	3220	160 SX CMT
SURF	8.625	267		150 SX CMT

#164¹³

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/14/2005 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Perfs 4450' - 4460'; sand 4400' & 4 sxs; 1200' & 35 sxs; 800' & 35 sxs; circ 320'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 07/14/2005 2:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perforations sanded to 4400' and 4 sacks of cement. Recovered 3220' of 4-1/2" casing. Pulled casing to 1200' and spotted 35 sacks of cement. Pulled casing to 800' and spotted 35 sacks of cement. Pulled casing to 320' and circulated cement to surface.

Allied Cement

60/40 posmix with 4% gel

Perfs:

Top	Bot	Thru	Comments
4450	4460		

**RECEIVED
KCC DISTRICT #2
JUL 20 2005
WICHITA, KS**

Remarks:

Plugged through: CSG

District: 02

Signed [Signature]
(TECHNICIAN)

INVOICED
DATE 8-01-05
INV. NO. 2006060221

RECEIVED
AUG 01 2005
KCC WICHITA