

3 022760

15-207.19538-00-00

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078
Wichita, Kansas 67202API NUMBER NE SENE
SW, NE, NE 1/4 CONTROL NO. 20050019-017
Sec/Twp/Rge S.28-T.25S.-R.17E.3794 feet from south section line185 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Operator: STATE OF KANSASName & FEE FUND PLUGGING

Address _____

AB oil well ☒ Gas Well _____ SWD Well/ Input Well _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W OIL WELL SERVICE, INC.Lic. # 3097Address: 19450 FORD ROAD, CHANUTE, KANSAS 66720Company to plug at: Hour: 1:00P.M. Day: _____ 12 Month: 7 2005Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 750' THAT HADBEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATEAS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT INSIDE AND OUTSIDE THE2" CASING.

RECEIVED

JUL 25 2005

KCC WICHITA

Plugging Proposal Received by: CLAYTON P. TITELPlugging attended by Agent: All _____ Part X _____ TECHNICIAN
None _____Operations Completed: Hour: 4:00P.M. Day: _____ 12 Month: 7 2005Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 700'. CEMENTWAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM 2" CASING ATSURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 7" ANNULUSTO 450'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROMTHE 7" SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENTWAS FILLED FROM SURFACE. 121 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.Remarks: (GPS SESSION PT. NO.1) (THIS WELL WAS NOT NUMBERED ON THE LEASE MAP)(If additional description is necessary, use BACK of this form.)I DID observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN

Bm