

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Scheck Oil Operation
Address: 225 Main Russell, Kansas 67665
Phone: (785) 483-3404 Operator License #: 9292
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Greg Eves Gary Winters (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-159-01925-00-00
Lease Name: J.R. Lansing "A"
Well Number: 2
Spot Location (OOQQ): _____ SE . NE . SW
1650 Feet from _____ North / South Section Line KCC BEM 8-2-05 RSDMS CP2/3
3630 Feet from East / West Section Line
Sec. 25 Twp. 18 S. R. 8 East West
County: Rice
Date Well Completed: _____
Plugging Commenced: 7-25-05
Plugging Completed: 7-26-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				10-3/4"	202'	None
				7"	3152'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 3100' and 7 sacks cement. Perforated well @1050', 700' and 260'. Ran 2-3/8" tubing to 1050', pumped 50 sacks cement, pulled up to 700', pumped 50 sacks cement, pulled up to 260' & circulated to surface with 60 sacks. Tied onto 7", pumped 70 sacks, 60/40 pos, 4% gel. Plugging Complete

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529
Address: P.O. Box 467 Chase, Kansas 67524
Name of Party Responsible for Plugging Fees: Scheck Oil Operation
State of Kansas County: Rice ss.


RECEIVED
AUG 03 2005

Mike Kelso (Employee of Operator) or (Operator) on above-described well being plugged, sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mike Kelso
(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 1st day of August, 2005

Irene Herzberg My Commission Expires: _____
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KCC
BEM
8-3-05
CP2/3

Bm