

API NUMBER <sup>15-</sup> 195-22,291-00-00

LEASE NAME Greg Kroeger

RECEIVED

AUG 05 2005

KCC WICHITA

TYPE OR PRINT

NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER 1-23  
980 Ft. from S Section Line  
1470 Ft. from E Section Line  
 SEC. 23 TWP. 13S RGE. 21W ~~XEN~~ or (W)  
 COUNTY Trego

LEASE OPERATOR DOWNING-NELSON OIL CO., INC.  
 ADDRESS P.O. Box 372 Hays, KS 67601  
 PHONE# (785) 621-2610 OPERATORS LICENSE NO. 30717

Date Well Completed 5/21/05  
 Plugging Commenced 12:30PM 5/21/05  
 Plugging Completed 3:00PM 5/21/05

Character of Well D & A  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5/20/05 (date)  
 by Roger Moses (KCC District Agent's Name).

Is ACO-1 filled? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation None Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4050

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		Surface	222	8 5/8	221.79	None


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set  
 1st Plug @ 1650' W/25sks 15sks In Rat Hole Circulated 1st Plug 15 Minutes W/53 Vis Mud  
 2nd Plug @ 875' W/100sks 10sks In Mouse Hole Plugs displaced with mud  
 3rd Plug @ 275' W/40sks Total 200sks 60/40Poz 6%GelW/1#CF/sk By Allied Cementing  
 4th Plug @ 40' W/10sks Completed @ 3:00PM 5/21/05

Name of Plugging Contractor Discovery Drilling Co., Inc. License No. 31548  
 Address P.O. Box 763 Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: DOWNING-NELSON OIL CO., INC.

STATE OF \_\_\_\_\_ COUNTY OF \_\_\_\_\_, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Ala Downey VP  
 (Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 14 day of May, 2005

[Signature]  
 Notary Public

My Commission Expires: 1-10-07  
 USE ONLY ONE SIDE OF EACH FORM