

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Oxy USA, Inc.
Address: PO Box 2528 Liberal KS 67905
Phone: (620)629-4200 Operator License #: 5447
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 5-23-05 (Date)
by: Jim Holland (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Council Grove Depth to Top: 2836 Bottom: 2892 T.D. 3050

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-067-20417-00-00
Lease Name: Dew A
Well Number: 2 SW
Spot Location (QQQQ): SE-SW-SW-NE
2540 Feet from North / South Section Line
2340 Feet from East / West Section Line
Sec. 3 Twp. 27S. R. 35 East West
County: Grant
Date Well Completed: 7-28-78
Plugging Commenced: 6-23-05
Plugging Completed: 6-24-05

KCC
BEM
8-3-05
REDMS
Per Footages

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records | | Casing Record (Surface Conductor & Production) | | | | |
|---------------------------|---------|--|----|-------|--------|------------|
| Formation | Content | From | To | Size | Put In | Pulled Out |
| | | | | 8 5/8 | 796 | - |
| | | | | 4 1/2 | 3049 | 1097 |
| | | | | | | |
| | | | | | | |

RECEIVED
AUG 03 2005

KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

CIBP + 2sx 2790 to 2770. Loaded 4 1/2 w/mud to 1900, mixed 15sx cmt from 1900 to 1700, mud to 0. Shot & pulled 4 1/2 to 825. Circ. hole w/mud & mixed 50 sx 825 to 675. 10 sx 40 to 0 Capped 8 5/8 3 ft. below G.L.


Name of Plugging Contractor: SARGENT AND HORTON PLUGGING, INC. License #: 31151
Address: RT. 1, Box 49 BA Tyrone, OK 73951-9731
Name of Party Responsible for Plugging Fees: Oxy USA Inc. 1701 N. Kansas Rd Box 2528 Liberal, KS. 67950
State of Kansas, Seward County, Seward, ss.

Kenny Andrews (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) PO Box 2528 Liberal, KS. 67950

SUBSCRIBED and SWORN TO before me this 29 day of July, 2005

Anita Peterson My Commission Expires: Oct. 1, 2005
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

BW