

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Mike Kelso Oil, Inc.
Address: P.O. Box 467 Chase, Kansas 67524
Phone: (620) 938-2943 Operator License #: 31528
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Case Morris (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well to be attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-167-05492-00-00
Lease Name: Brown "B"
Well Number: 1
Spot Location (OOQQ): _____ SE _____ SW
330 Feet from _____ North / South Section Line
2970 Feet from East / _____ West Section Line
Sec. 27 Twp. 15 S. R. 12 _____ East West
County: Russell
Date Well Completed: 6-3-49
Plugging Commenced: 7-20-05
Plugging Completed: 7-22-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	148'	None
				5-1/2"	3260'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Rods parted 44 rods down, tubing parted 18 jts. down, couldn't fish either one. Ran tubing to 550', pumped 150 sacks cement, pulled tubing out, ran in 1" with 558' of 2-3/8", pumped 95 sacks cement & circulated. Pumped 60 sacks cement down 5-1/2", pumped 35 sacks down surface. 60/40 pos Plugging Complete. 10% ge

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529
Address: P.O. Box 467 Chase, Kansas 67524
Name of Party Responsible for Plugging Fees: Mike Kelso Oil
State of Kansas County, Rice ss.

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) *Mike Kelso*
(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 1st. day of August, 2005

Irene Herzberg
Notary Public

My Commission Expires: _____
NOTARY PUBLIC - State of Kansas
IRENE HERZBERG
My Appt. Exp. 8-24-05

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
AUG 03 2005
KCC WICHITA

Brown