

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-111-20427-00-00
Spot: E2NE Sec/Twnshp/Rge: 5-17S-13E
1320 feet from N Section Line, 660 feet from E Section Line
Lease Name: BRIGGS Well #: 1-5
County: LYON Total Vertical Depth: 2770 feet

Operator License No.: 4549
Op Name: ANADARKO PETROLEUM CORPORATI
Address: 1201 LAKE ROBBINS DRIVE
THE WOODLANDS, TX 77380

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	2764	850	330 SX CMT
SURF	9.625	241	4	180 SX CMT

#90⁰³

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/12/2004 8:00 AM
Plug Co. License No.: 7407 Plug Co. Name: EAGLE WELL SERVICE
Proposal Rcvd. from: MICHEAL POND Company: _____ Phone: (620) 482-1006

Proposed Plugging Method: PLACE 2 SX HULLS AND 30 SX CMT TO COVE PERFS. CUT OFF 7" CASING @ 1200'. SPOT 20 SX CEMENT FROM 1150' - 1200'. PUMP 120 SX CLASS H CMT. FROM SURFACE DOWN. CUT OFF AND CAP 9-5/8" CASING AT 4' BELOW GL. SPACE HEAVY MUD BETWEEN CMT PLUGS.

Plugging Proposal Received By: _____ WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/12/2004 5:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 1950' pumped 2 sxs hulls & 30 sxs cement, pulled tubing out shot casing @ 1200' pumped 20 sxs cement, from 1150' to 12100' pumped 120 sxs cement from surface down .

Perfs:

Top	Bot	Thru	Comments
1942	1944		
1908	1910		
1856	1857		

RECEIVED
KCC DISTRICT #3
AUG 1 2005 MA
CHANUTE, KS

RECEIVED
AUG 04 2005
KCC WICHITA

Remarks:
Plugged through: TBG

District: 03 Signed Michael Heffern (TECHNICIAN)

INVOICED
DATE 8-9-05
TEL NO. 2006060258